A. TYPE OF WELL Gas Well Coalbed Methane Well: NO A. TYPE OF WELL Gas Well Coalbed Methane Well: NO S. FIELD OR WILDCAT NATURAL BUTTES S. UNIT or COMMUNITIZATION AGREEMENT NAME NATURAL BUTTES															
2. TITLE OF WORKE PREMITTION PLAN POWER PREMITTION		STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES AMENDED REPORT													
DRILL PEW WIELL Gos Well Collect Methan Viel NO S. UNITY COSMUNITY TO COMMUNITY COMMUNI	APPLICATION FOR PERMIT TO DRILL														
## ATTRICO MULTICATION AGREEMENT NAME ## AND CORPORATION ## AND CORPO	2. TYPE OF WORK												BUTTES		
## ADDRESS OF OPERATOR ## ADDRESS OF OPERATOR ## PO Sou 175776 Deliver, CO, SQL17 ## ADDRESS OF OPERATOR ## PO Sou 175776 Deliver, CO, SQL17 ## ADDRESS OF SUPFACE OWNER (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 Teley) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OWNER PIDOR (PIDOR 2 TELEY) ## ADDRESS OF SUPFACE OWNER PIDOR (PI	4. TYPE OF	WELL												ENT NAM	1E
ADDRESS OF OPERATOR P.O. Box 173773, Dennes, CO., 90217 11. MINERAL OWNERSHIP FEE 12. SURFACE OWNER PRIOR (if box 12 = "fee") 12. SURFACE OWNER PRIOR (if box 12 = "fee") 13. MINERAL OWNERSHIP FEE 14. SURFACE OWNER PRIOR (if box 12 = "fee") 14. SURFACE OWNER (if box 12 = "fee") 15. SURFACE OWNER E-MAIL (if box 12 = "fee") 15. SURFACE OWNER E-MA	6. NAME OF OPERATOR 7. OPERATOR PHONE														
11. MINERAL LIEASE NUMBER 12. SUPPLACE OWNER RIVE FEDERAL	8. ADDRES	8. ADDRESS OF OPERATOR 9. OPERATOR E-MAIL													
13. NAME OF SURFACE OWNER (He box 12 = *ree)* 14. SURFACE OWNER PROBLE (He box 12 = *ree)* 14. SURFACE OWNER PROBLE (He box 12 = *ree)* 15. ADDRESS OF SURFACE OWNER (He box 12 = *ree)* 16. SURFACE OWNER E-MAIL (He box 12 = *ree)* 17. NIDIAN ALLOTTEE OR TRIBE NAME (He box 12 = *ree)* 16. SURFACE OWNER E-MAIL (He box 12 = *ree)* 17. NIDIAN ALLOTTEE OR TRIBE NAME (He box 12 = *ree)* 18. SURFACE OWNER E-MAIL (He box 12 = *ree)* 17. NIDIAN ALLOTTEE OR TRIBE NAME (He box 12 = *ree)* 18. SURFACE OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER PROBLEMS NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER PROBLEMS NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL NORMAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL DIRECTIONAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL OWNER E-MAIL (He box 12 = *ree)* 19. SLANT VERTICAL OWNER E-MAIL (He box				P.O. Box 1/3//8			SHIP						anadarko	.com	
15. ADDRESS OF SURFACE OWNER (if box 12 = "text") 17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = "INDIAN") 18. INTEND TO COMMINGLE PRODUCTION FROM WOLTH-IF FORMATION'S 19. SLANT VERTICAL DIRECTIONAL NO NO NO DIRECTIONAL NO DIRECTIONAL NO NO DIRECTIONAL NO NO DIRECTIONAL NO NO DIRECTIONAL NO DIRECTION			UTU0147566		FED	DERAL (III) IND	DIAN 🔵	STATE () FEE		~				EE 💮
15. INTEND TO COMMINGLE PRODUCTION FROM WILLTHE FORMATIONS 19. SLANT 15. INTEND TO COMMINGLE PRODUCTION FROM WILLTHE FORMATIONS 19. SLANT 15. INTEND TO COMMINGLE PRODUCTION FROM WILLTHE FORMATIONS 19. SLANT 15. INTEND TO COMMINGLE PRODUCTION FROM WILLTHE FORMATIONS 19. SLANT 15. INTEND TO COMMINGLE PRODUCTION FROM WILLTHE FORMATIONS 19. SLANT 15. INTEND TO COMMINGLE PRODUCTION FROM WILLTH	13. NAME	OF SURFACE	OWNER (if box 12	= 'fee')							14. SURFACE OWNE	R PHONE	(if box 12	= 'fee')	
No. No. No. No. No. No. No	15. ADDRE	SS OF SURFA	CE OWNER (if box	12 = 'fee')							16. SURFACE OWNE	R E-MAIL	(if box 12	! = 'fee')	
20. LOCATION OF WELL FOOTAGES QTR-QTR SECTION TOWNSHIP RANGE MERIDAN LOCATION AT SURFACE 691 FNL 2150 FWL NEW 22 9.0 S 21.0 E 5 Top of Uppermost Producing Zone 85 FNL 2150 FWL NEW 22 9.0 S 21.0 E 5 Top of Uppermost Producing Zone 85 FNL 2150 FWL NEW 22 9.0 S 21.0 E 5 TOP OF Uppermost Producing Zone 85 FNL 2150 FWL NEW 22 9.0 S 21.0 E 5 TOP OF Uppermost Producing Zone 85 FNL 2150 FWL NEW 22 9.0 S 21.0 E 5 TOP OF Uppermost Producing Zone 85 FNL 2150 FWL NEW 22 9.0 S 21.0 E 5 TOP OF Uppermost Producing Zone 85 FNL 2150 FWL NEW 22 9.0 S 21.0 E 25. DISTANCE TO NEAREST LEASE LINE (Feet) 85 20. STANCE TO NEAREST LEASE LINE (Feet) 85 20. STANCE TO NEAREST LEASE LINE (Feet) 85 27. ELEVATION - GROUND LEVEL 4823 TOP OF Uppermost Producing Zone 85 FNL 2150 FWL NEW 25. DISTANCE TO NEAREST LEASE LINE (Feet) 85 20. STANCE TO NEAREST SIN DELINIO UNIT SITUE LINE UNIT SITU			R TRIBE NAME					RODUCTION	FROM		19. SLANT				
COLATION AT SURFACE	(II DOX 12		te Indian Tribe		YES	(Submit C	Commingli	ing Application	on) NC		VERTICAL DI	RECTION	AL D H	HORIZON	ral 🔵
Top of Uppermost Producing Zone 85 FNL 2150 FWL NENW 22 9.0 \$ 21.0 \$ S	20. LOCA	TION OF WELL			FOOTAGE	ES	QTR	R-QTR	SE	CTION	TOWNSHIP	R	ANGE	МЕ	RIDIAN
A Total Depth	LOCATIO	N AT SURFACE		691	FNL 2010	0 FWL	NE	ENW		22	9.0 S	2	1.0 E		S
22. DISTANCE TO NEAREST LEASE LINE (Feet) 23. NUMBER OF ACRES IN DRILLING UNIT 160 1	Top of Up	permost Prod	ucing Zone	85	FNL 2150	FWL	NE	ENW		22	9.0 S	2	1.0 E		S
String Hole Size Length Weight Grade & Thread Max Mud Wt. Cement Sacks Yeld Weight Surface S	At Total I	Depth		85	FNL 2150	FWL	NE	ENW	22 9.0 S		2	1.0 E		S	
Capitled For Drilling or Completed ABADI NUMBER	21. COUN	ГҮ	UINTAH		22. DI	STANCE TO NEA			eet)		23. NUMBER OF ACR			IT	
27. ELEVATION - GROUND LEVEL 4823 28. BOND NUMBER 29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE							or Compl	leted)	POOL				TVD: 111	95	
A A A B A B B B B B	27. ELEVA	TION - GROUN	ID LEVEL		28. BC	OND NUMBER	446	6				LING WA	TER /		
String Hole Size Casing Size Length Weight Grade & Thread Max Mud Wt. Cement Sacks Vield Weight Surf 11 8.625 0 - 2880 28.0 J-55 LT&C 0.2 Type V 18.0 1.15 15.8 15.8			4823				WYB00	00291			WATER RIGHTS APPR			PPLICAB	LE
Surf 11										n					
Prod 7.875 4.5 0 - 11259 11.6 HCP-110 LT&C 13.0 Premium Lite High Strength 350 3.38 12.0 50/50 Poz 1600 1.31 14.3 ATTACHMENTS WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) NAME Laura Abrams TITLE Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com APPROVAL APPROVAL APPROVAL APPROVAL				_						-					
Prod 7.875 4.5 0 - 11259 11.6 HCP-110 LT&C 13.0 Premium Lite High Strength 350 3.38 12.0 50/50 Poz 1600 1.31 14.3 ATTACHMENTS VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) NAME Laura Abrams TITLE Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com APPROVAL APPROVAL APPROVAL	Suii	- 11	0.025	0 - 2000	20.0	J-55 L1	IQU	0.	2		**				
ATTACHMENTS VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) NAME Laura Abrams TITLE Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura Abrams@anadarko.com APPROVAL APPROVAL	Prod	7.875	4.5	0 - 11259	11.6	HCP-110	LT&C	13	.0	Pre		ength			
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER COMPLETE DRILLING PLAN AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) TOPOGRAPHICAL MAP NAME Laura Abrams TITLE Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com APPROVAL											50/50 Poz		1600	1.31	14.3
WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER POPULATION TO POPULATION T						А	TTACHN	WENTS							
AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE) FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) NAME Laura Abrams TITLE Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com APPROVAL APPROVAL		VER	IFY THE FOLLO	WING ARE AT	FACHED I	IN ACCORDAN	ICE WITH	H THE UTA	AH OIL A	AND GAS	CONSERVATION G	SENERA	L RULES		
Image: Directional survey plan (if directionally or horizontally drilled) Image: Topographical Map NAME Laura Abrams Tittle Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com API NUMBER ASSIGNED 43047525580000 APPROVAL APPROVAL	₩	ELL PLAT OR M	AP PREPARED BY	LICENSED SURVE	YOR OR E	NGINEER		✓ COM	PLETE D	RILLING P	LAN				
NAME Laura Abrams TITLE Regulatory Analyst II PHONE 720 929-6356 SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com API NUMBER ASSIGNED 43047525580000 APPROVAL	AFF	FIDAVIT OF STA	TUS OF SURFACE	OWNER AGREEM	NENT (IF FE	EE SURFACE)		FORM	1 5. IF OP	PERATOR I	S OTHER THAN THE L	EASE OW	NER		
SIGNATURE DATE 04/27/2012 EMAIL Laura.Abrams@anadarko.com API NUMBER ASSIGNED 43047525580000 APPROVAL	DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED) TOPOGRAPHICAL MAP														
API NUMBER ASSIGNED APPROVAL APPROVAL	NAME Laura Abrams TITLE Regulatory Analyst II								PHONE 720 929-6356						
43047525580000	SIGNATURE DATE 04/27/2012							EMAIL Laura.Abrams@anadarko.com							
			0000		APPROV	/AL				Berm	DANNI it Manager				

NBU 921-22C Pad Drilling Program

1 of 4

Kerr-McGee Oil & Gas Onshore, L.P.

NBU 921-22C1BS

Surface: 691 FNL / 2010 FWL NENW BHL: 85 FNL / 2150 FWL NENW

Section 22 T9S R21E

Unitah County, Utah Mineral Lease: UTU 0147566

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. & 2.a <u>Estimated Tops of Important Geologic Markers</u>: Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,548'	
Birds Nest	1,891'	Water
Mahogany	2,430'	Water
Wasatch	4,975'	Gas
Mesaverde	7,918'	Gas
Sego	10,136'	Gas
Castlegate	10,199'	Gas
MN5	10,595'	Gas
TVD =	11,195'	
TD =	11,259'	

2.c Kerr McGee Oil & Gas Onshore LP (Kerr McGee) will either drill to the the Blackhawk formation, which is part of the Mesaverde formation, or the Wasatch/Mesaverde formation. If Kerr McGee drills to the Blackhawk formation (part of the Mesaverde formation), please refer to MN5 as the bottom formation. The attached Blackhawk Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the deeper formation.

If Kerr McGee drills to the Wasatch/Mesaverde formation please refer to Sego as the bottom formation. The attached Wasatch/Mesaverde Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the depths the Wasatch/Mesaverde formations are found.

NBU 921-22C Pad Drilling Program 2 of 4

3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

4. <u>Proposed Casing & Cementing Program:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

5. Drilling Fluids Program:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

6. Evaluation Program:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

7. <u>Abnormal Conditions</u>:

7.a Blackhawk (Part of Mesaverde Formation) Target Formation

Maximum anticipated bottom hole pressure calculated at 7,389 psi (0.66 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,977 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

7.b Wasach/Mesaverde Target Formation

Maximum anticipated bottom hole pressure calculated at 6,487 psi (0.64 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,243 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. <u>Variances:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program Onshore Order #2 – Air Drilling Variance

 $Kerr-McGee\ Oil\ \&\ Gas\ Onshore\ LP\ (KMG)\ respectfully\ requests\ a\ variance\ to\ several\ requirements\ associated\ with\ air\ drilling\ outlined\ in\ Onshore\ Order\ 2$

- · Blowout Prevention Equipment (BOPE) requirements;
- · Mud program requirements; and
- Special drilling operation (surface equipment placement) requirements associated with air drilling.

NBU 921-22C Pad Drilling Program
3 of 4

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill a 11inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

NBU 921-22C Pad Drilling Program
4 of 4

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to Onshore Order 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). This well is not an exploratory well and is being drilled in an area where the formation integrity is well known. Additionally, when an FIT is run with the mud weight as required, the casing shoe frequently breaks down and causes subsequent lost circulation when drilling the entire depth of the well.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.

10. Other Information:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program


NBU 921-22C Pad Drilling Program

1 of 2



KERR-McGEE OIL & GAS ONSHORE LP BLACKHAWK DRILLING PROGRAM

COMPANY NAME KER	R-McGEE OIL &	GAS ONSHOR	E LP		DATE	January 3	2012		
WELL NAME NB	U 921-22C1B	S		TD	11,195'	TVD	11,259' MD		
FIELD Natural Butte	S	COUNTY	Uintah	STATE Uta	h	FINIS	SHED ELEVATION _	4,823'	
SURFACE LOCATION	NENW	691 FNL	2010 FWL	Sec 22	T 9S	R 21E			
	Latitude:	40.026928	Longitude	: -109.54	0129		NAD 83		
BTM HOLE LOCATION	NENW	85 FNL	2150 FWL	Sec 22	T 9S	R 21E			
	Latitude:	40.028588	Longitude	: -109.53	9628		NAD 83		
OBJECTIVE ZONE(S)	BLACKHAWK	•	•	•					
ADDITIONAL INFO Regulatory Agencies: BLM (Minerals). Lite Indian Tribe (Surface). LIDOGM Tri-County Health Dept									



NBU 921-22C Pad Drilling Program
2 of 2



KERR-McGEE OIL & GAS ONSHORE LP BLACKHAWK DRILLING PROGRAM

CASING PROGRAM

CONDUCTOR SURFACE

PRODUCTION

									LTC	DQX
SIZE	INTERVAL			WT.	GR.	CPLG.	BURST	COLLAPSE	TE	NSION
14"	0-40'									
							3,390	1,880	348,000	N/A
8-5/8"	0	to	2,880	28.00	IJ-55	LTC	1.87	1.39	4.93	N/A
							10,690	8,650	279,000	367,174
4-1/2"	0	to	5,000	11.60	HCP-110	DQX	1.19	1.14		3.51
4-1/2"	5,000	to	11,259'	11.60	HCP-110	LTC	1.19	1.14	4.80	

Surface Casing:

(Burst Assumptions: TD = 13.0 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 9000 psi) 0.66 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE LEAD 500'		Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1		+ 0.25 pps flocele				
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
		+ 2% CaCl + 0.25 pps flocele				
SURFACE		NOTE: If well will circulate water to	surface, op	tion 2 will be	utilized	
Option 2 LEAD	2,380'	65/35 Poz + 6% Gel + 10 pps gilsonite	220	35%	11.00	3.82
		+ 0.25 pps Flocele + 3% salt BWOW				
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
		+ 0.25 pps flocele				
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION LEAD	4,469'	Premium Lite II +0.25 pps	350	35%	12.00	3.38
		celloflake + 5 pps gilsonite + 10% gel				
		+ 0.5% extender				
TAIL	6,790'	50/50 Poz/G + 10% salt + 2% gel	1,600	35%	14.30	1.31
		+ 0.1% R-3				

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Survev	's will	be	taken	at	1.000'	minimum	intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized

	Most rigs have i vi System for muc	Thorntoning. If no r v r is available, visual monitoning will be utilized.		
DRILLING	ENGINEER:		DATE:	
		Nick Spence / Danny Showers / Chad Loesel	•	
DRILLING	SUPERINTENDENT:		DATE:	
		Kenny Gathings / Lovel Young	•	

DESIGN FACTORS


^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

NBU 921-22C Pad Drilling Program

1 of 2



KERR-McGEE OIL & GAS ONSHORE LP WASATCH/MESAVERDE DRILLING PROGRAM



NBU 921-22C Pad Drilling Program 2 of 2



KERR-McGEE OIL & GAS ONSHORE LP

WASATCH/MESAVERDE DRILLING PROGRAM

CASING PROGRAM

CONDUCTOR

SURFACE PRODUCTION

									LTC	DQX
SIZE	INT	ERVA	L	WT.	GR.	CPLG.	BURST	COLLAPSE	TENSION	
14"	(0-40'								
							3,390	1,880	348,000	N/A
8-5/8"	0	to	2,880	28.00	IJ-55	LTC	1.87	1.39	4.93	N/A
							7,780	6,350		267,035
4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	0.96		2.79
							10,690	8,650	223,000	
4-1/2"	5,000	to	10,200'	11.60	HCP-110	LTC	1.53	1.31	4.57	

Surface Casing:

(Burst Assumptions: TD =

12.5 ppg)

0.73 psi/ft = frac gradient @ surface shoe

DESIGN FACTORS

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

(Collapse Assumption: Fully Evacuated Casing, Max MW)

•

cholor riscampusitor rai rrolgiti or casing 2 asyn asin or mate

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @

7000

0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

	FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD				
SURFACE LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15				
Option 1		+ 0.25 pps flocele								
TOP OUT CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15				
		+ 2% CaCl + 0.25 pps flocele								
SURFACE		NOTE: If well will circulate water to surface, option 2 will be utilized								
Option 2 LEAD	2,380'	65/35 Poz + 6% Gel + 10 pps gilsonite	220	35%	11.00	3.82				
		+ 0.25 pps Flocele + 3% salt BWOW								
TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15				
		+ 0.25 pps flocele								
TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15				
PRODUCTION LEAD	4,470'	Premium Lite II +0.25 pps	350	35%	12.00	3.38				
		celloflake + 5 pps gilsonite + 10% gel								
		+ 0.5% extender								
TAIL	5,730'	50/50 Poz/G + 10% salt + 2% gel	1,350	35%	14.30	1.31				
		+ 0.1% R-3								

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SU	IR.	F	٩C	Έ
			-	_

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well.

1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING	ENGINEER:

Nick Spence / Danny Showers / Chad Loesel


DAIL.	
DATE:	

DRILLING SUPERINTENDENT:


Kenny Gathings / Lovel Young

^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

EXHIBIT A NBU 921-22C1BS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK




			SURFACE	POSITIO	N	BOTTOM HOLE					
WELL NAME	NAE			NAI			NAE		NAI		
NBU	LATITUDE 40°01'36.629"	109°32'25.		TUDE 36.756		723' FNL	LATITUDE	LONGITUDE	LATITUDE	LONGITUDE	FOOTAGES
921-22C GR	40.026841°	109 32 23.	. – .		109 32 22.643 109.539623°	1959' FWL					
NBU 921-22F4BS	40°01'36.732" 40.026870°	109°32'24.		'36.859" 5905°		712' FNL	40°01'23.275" 40.023132°	109°32'22.677" 109.539632°	40°01'23.402" 40.023167°	109°32'20.199"	2073¹ FNL
921-22F4BS NBU	40.026870° 40°01'36.784"	109.54025 109°32 24.		36.911"	109.539562° 109°32'22.315"	1976' FWL 707' FNL	40.023132° 40°01'26.545"	109.539632° 109°32'22.676"	40.02316/° 40°01'26.672"	109.538944° 109°32'20.198"	2149' FWL 1742' FNL
921-22F1CS	40.026884°	109.540220	0° 40.02		109.539532°	1984' FWL	40.024040°	109.539632°	40.024076°	109.538944°	2149¹ FWL
NBU 921-22F1BS	40°01'36.836" 40.026899°	109°32'24. 109.54019	0° 40.02		109.539501°	701' FNL 1993' FWL	40°01'29.825" 40.024952°	109°32'22.676" 109.539632°	40°01'29.952" 40.024987°	109°32'20.198" 109.538944°	1410' FNL 2149' FWL
NBU 921-22C4CS	40°01'36.888" 40.026913°	109°32'24.			109°32'22.096" 109.539471°	696' FNL 2001' FWL	40°01'33.106" 40.025863°	109°32'22.676" 109.539632°	40°01'33.233" 40.025898°	109°32'20.198" 109.538944°	1078' FNL
NBU	40°01'36.939"	109.34013 109°32'24.	_	37.066"		691' FNL	40°01'42.916"	109.539632° 109°32'22.662"	40°01'43.044"	109.538944° 109°32'20.184"	2149' FWL 85' FNL
921-22C1BS	40.026928° 40°01'36.321"	109.540129		5963° '36.448"	109.539441°	2010' FWL	40.028588°	109.539628°	40.028623°	109.538940°	2150' FWL
NBU 192	40.026756°	109°32'24. 109.54011			109°32'21.945" 109.539429°	753' FNL 2013' FWL					
			RE	LATIVE (COORDINATES	- From Surface	Position to Bott	om Hole			
WELL NAME	NORTH	EAST	WELL NAM	IE NO	ORTH EAS		NAME NOR	TH EAST	WELL NAM	IE NORTH	EAST
NBU 921-22F4BS	-1362.2	172.1'	NBU 921-22F1C	, -1	036.51 163.	8 NBU 921-22	-709	.7' 155.6'	NBU 921-22C4C	s -382.9'	147.4'
WELL NAME	NORTH	EAST	/		\		1			\	
NBU 921-22C1BS	604.9'	140.8'	//		7. \		4			1	
32. 220100				Z	/ ¹ / ₈ /		1.5				\
		/ /	/	ST. COCTION.	TO CHES WHELL ST.	\	$\begin{array}{c} Az=13.10417^{\circ} \\ N13^{\circ}06^{\circ}15^{\circ}\overline{F} \cdot 621.03^{\circ} \\ (To Bottom Hole) \end{array}$			/	
				હ	(1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		41, 62/ 0/e,			./	
	/ /				21,5	17.00 123	$N_{13} \frac{Az=13.10417}{(70 \text{ Bottom Hole})}$				\
			Ź	. 4			:13 15' '0n,	1 - Q"	£ /0		
			ેં	<,	1 0 20 TO	.08 F	\z= \ \ \sqrt{0}C_ \sqrt{0}	0.58,20	306		آ ا
ľ /				tisk.	8 7 85	૱ૢ <i>૾</i> ૢૢૢૢૢૢૢૢ	3°C 0 B	458 58.AC	,-		
				47	180 39 1883 1 C CR (ST. 191 180 191 191 191 191 191 191 191 191 191 19	1 5 S	12 C	N58°28'59" A1 "58.48			
						10 10 10 10 10 10 10 10 10 10 10 10 10 1	1 /	1		ı	
				· · · · ·	Sold Signer	10/10/10				,	•
					336 FX	0,	▼				\ \ 7
				-	ر کرون کر	> P - >	1/2			1	'V
	/				F.F.		30°				
						7. SE	CASA S				
						ا روسی ا	1.43				M
						TASK .	\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \\ \				
	/	ACIC OF DE	EADINICOU	TUEF	A CT LINE OF	1 2	× 4/ 80	•			
			:arings is F Section		AST LINE OF			38° 58.5			
			/HICH IS T			'	50 Th (5 000			
	G	LOBAL PC	SITIONIN	G SATEI	LITE	<u> </u>	8.1218° 55.91	3.5°			
	О	BSERVATI	ons to B	EAR NO	0°07 ' 07 " W.	&		•			
\						(TO F		i			
\) B(25 11 1 5 11 1	186			
						Botto	0E77.5	150			
						S = S	S12 019 1-1	/ 70 /	-		
\	.09	30'	_0		.09	Hole) - Az= 07°1	2°22'00 70 Both 1049.34				
\	\ <u> </u>					77 (e)	2/0 80 9.3	16.03			
	\		664:-			72. 56 Sott	# 150 H	7.6	58		
	\		SCALE			801 E-	13	33	.9 _A .		
	\					H371	1 12	726	P. O.		
	\					73.(5le)	1 6).55 \d			
	Gee Oil &			, LP		7 7	1		37		
1099 1	8th Street - De	nver, Color	ado 80202	!					\		
WEL	L PAD - N	NBU 92	21-22C			609		MBERL			35) 789-1365
\/\/I	ELL PAD INT	FRFFRFN	ICF PI AT				E			SURVEYING	
	- NBU 921-22			- 11	60.12	TTING ::	C DATE	209 NORTH :		RNAL, UTAH 840	
N	BU921-22F1C	S,NBÚ 921	-22F1BS,			ULTING, LLO Orth Main Stre	7-19-	-11	SURVEYED B	BY: W.W.	SHEET NO:
	U 921-22C4CS CATED IN SEC					an WY 82801	II DATI	DRAWN:	DRAWN BY:	T.J.R.	7
	.B.&M., UINT	,	, ,			307-674-060	9	CALE: 1" = 60'	Date Last Rev	vised:	7 OF 10
					Fax 3	607-674-0182		C. I. = 00			7 OF 18


S.L.B.&M., UINTAH COUNTY, UTAH

209 NORTH 300 WEST - VERNAL, UTAH 84078

RECEIVED: April 20, 2012

REVISED:








PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE

CAMERA ANGLE: SOUTHERLY



PHOTO VIEW: FROM BEGINNING OF PROPOSED ROAD

CAMERA ANGLE: NORTHWESTERLY

Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 921-22C

LOCATION PHOTOS NBU 921-22C GR, NBU 921-22F4BS, NBU 921-22F1CS, NBU 921-22F1BS, NBU 921-22C4CS & NBU 921-22C1BS LOCATED IN SECTION 22, T9S, R21E, S.L.B.&M., UINTAH COUNTY, UTAH.



CONSULTING, LLC 2155 North Main Street Sheridan WY 82801 Phone 307-674-0609 Fax 307-674-0182


TIMBERLINE


(435) 789-1365


11 OF 18


ENGINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078


ı	DATE PHOTOS TAKEN: 7-19-11	PHOTOS TAKEN BY: W.W.	SHEET NO:
П	DATE DRAWN: 8-22-11	DRAWN BY: T.J.R.	11
	Date Last Revised:		11 OF 18














Kerr-McGee Oil & Gas Onshore, LP WELL PAD - NBU 921-22C WELLS – NBU 921-22C GR, NBU 921-22F4BS, NBU 921-22F1CS, NBU 921-22F1BS, NBU 921-22C4CS & NBU 921-22C1BS Section 22, T9S, R21E, S.L.B.&M.

From the intersection of U.S. Highway 40 and 500 East street in Vernal, Utah, proceed in an easterly then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45. Exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 17.7 miles to a Class D County Road to the southwest. Exit right and proceed in a southwesterly direction along the Class D County Road approximately 1.8 miles to a second Class D County Road to the north. Exit right and proceed in a northerly direction along the second Class D County Road approximately 1.4 miles to the proposed access road. Follow road flags in a northwesterly direction approximately 175 feet to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 44.4 miles in a southerly direction.

SHEET 18 OF 18

API Well Number: 43047 5 20 5 20 5 COUTAR - UTM (feet), NAD27, Zone 12N

Scientific Drilling


Vertical Section at 13.06° (1500 ft/in)


Site: NBU 921-22C PAD Well: NBU 921-22C1BS


Wellbore: OH

Design: PLAN #1 PRELIMINARY











US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N NBU 921-22C PAD NBU 921-22C1BS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

17 November, 2011



RECEIVED: April 20, 2012



SDI Planning Report



EDM5000-RobertS-Local Database:

Company: US ROCKIES REGION PLANNING Project: UTAH - UTM (feet), NAD27, Zone 12N

Site: NBU 921-22C PAD Well: NBU 921-22C1BS

Wellbore: ОН

PLAN #1 PRELIMINARY Design:

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Site NBU 921-22C PAD

GL 4823 & KB 4 @ 4827.00ft (ASSUMED) GL 4823 & KB 4 @ 4827.00ft (ASSUMED)

Minimum Curvature

Project UTAH - UTM (feet), NAD27, Zone 12N

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 (NADCON CONUS) Geo Datum: Zone 12N (114 W to 108 W) Map Zone:

Mean Sea Level

NBU 921-22C PAD, SECTION 22 T9S R21E Site

Northing: 14,539,182.62 usft Site Position: Latitude: 40° 1' 36.757 N From: Lat/Long Easting: 2,049,254.73 usft Longitude: 109° 32' 22.643 W **Position Uncertainty:** 0.00 ft Slot Radius: **Grid Convergence:** 0.94 13.200 in

System Datum:

Well NBU 921-22C1BS, 691 FNL 2010 FWL

Well Position +N/-S 14,539,214.78 usft Latitude: 40° 1' 37.067 N 31.32 ft Northing: +E/-W 50.96 ft Easting: 2,049,305.17 usft Longitude: 109° 32' 21.988 W

0.00 ft Wellhead Elevation: **Ground Level:** 4,823.00 ft **Position Uncertainty**

Wellbore ОН Field Strength Magnetics **Model Name** Sample Date Declination Dip Angle (nT) (°) (°) IGRF2010 2011/11/16 11.04 65.87 52.297

PLAN #1 PRELIMINARY Design Audit Notes: Version: Phase: PLAN Tie On Depth: 0.00 Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 31.32 50.96 13.06

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	31.32	50.96	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	31.32	50.96	0.00	0.00	0.00	0.00	
937.50	12.75	13.06	932.25	100.13	66.93	2.00	2.00	0.00	13.06	
3,063.82	12.75	13.06	3,006.14	557.26	172.99	0.00	0.00	0.00	0.00	
3,792.39	0.00	0.00	3,728.72	635.90	191.24	1.75	-1.75	0.00	180.00	
11,258.68	0.00	0.00	11,195.00	635.90	191.24	0.00	0.00	0.00	0.00 P	BHL_NBU 921-22C



SDIPlanning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22C PAD

 Well:
 NBU 921-22C1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Site NBU 921-22C PAD

GL 4823 & KB 4 @ 4827.00ft (ASSUMED) GL 4823 & KB 4 @ 4827.00ft (ASSUMED)

True

ed Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
						` ,	, ,		
0.00 100.00	0.00 0.00	0.00 0.00	0.00 100.00	31.32 31.32	50.96 50.96	0.00 0.00	0.00 0.00	0.00 0.00	0.00 0.00
200.00	0.00	0.00	200.00	31.32	50.96	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	31.32	50.96	0.00	0.00	0.00	0.00
Start Build 2.		0.00	000.00	01.02	00.00	0.00	0.00	0.00	0.00
400.00	2.00	13.06	399.98	33.02	51.35	1.75	2.00	2.00	0.00
500.00 600.00	4.00 6.00	13.06 13.06	499.84 599.45	38.12 46.61	52.54 54.51	6.98 15.69	2.00 2.00	2.00 2.00	0.00 0.00
700.00	8.00	13.06	698.70	58.48	57.26	27.88	2.00	2.00	0.00
800.00	10.00	13.06	797.47	73.72	60.80	43.52	2.00	2.00	0.00
900.00	12.00	13.06	895.62	92.30	65.11	62.60	2.00	2.00	0.00
937.50	12.75	13.06	932.25	100.13	66.93	70.64	2.00	2.00	0.00
	hold at 937.50		000.01	44					
1,000.00	12.75	13.06	993.21	113.57	70.04	84.43	0.00	0.00	0.00
1,100.00	12.75	13.06	1,090.74	135.07	75.03	106.50	0.00	0.00	0.00
1,200.00 1,300.00	12.75 12.75	13.06 13.06	1,188.28 1,285.81	156.57 178.07	80.02 85.01	128.57 150.64	0.00 0.00	0.00 0.00	0.00 0.00
1,400.00	12.75	13.06	1,383.35	199.56	90.00	172.71	0.00	0.00	0.00
1,500.00	12.75	13.06	1,480.88	221.06	94.98	194.78	0.00	0.00	0.00
1,568.82	12.75	13.06	1,548.00	235.86	98.42	209.97	0.00	0.00	0.00
GREEN RIVE									
1,600.00	12.75	13.06	1,578.42	242.56	99.97	216.85	0.00	0.00	0.00
1,700.00	12.75	13.06	1,675.95	264.06	104.96	238.92	0.00	0.00	0.00
1,800.00	12.75	13.06	1,773.48	285.56	109.95	260.99	0.00	0.00	0.00
1,900.00	12.75	13.06	1,871.02	307.06	114.94	283.06	0.00	0.00	0.00
1,920.49	12.75	13.06	1,891.00	311.46	115.96	287.58	0.00	0.00	0.00
BIRDSNEST									
2,000.00	12.75	13.06	1,968.55	328.56	119.93	305.13	0.00	0.00	0.00
2,100.00	12.75	13.06	2,066.09	350.05	124.91	327.20	0.00	0.00	0.00
2,200.00	12.75	13.06	2,163.62	371.55	129.90	349.27	0.00	0.00	0.00
2,300.00	12.75	13.06	2,261.16	393.05	134.89	371.34	0.00	0.00	0.00
2,400.00	12.75	13.06	2,358.69	414.55	139.88	393.41	0.00	0.00	0.00
2,473.11	12.75	13.06	2,430.00	430.27	143.53	409.54	0.00	0.00	0.00
MAHOGANY									
2,500.00	12.75	13.06	2,456.22	436.05	144.87	415.48	0.00	0.00	0.00
2,600.00	12.75	13.06	2,553.76	457.55	149.85	437.55	0.00	0.00	0.00
2,700.00	12.75	13.06	2,651.29	479.05	154.84	459.62	0.00	0.00	0.00
2,800.00	12.75	13.06	2,748.83	500.55	159.83	481.69	0.00	0.00	0.00
2,900.00	12.75	13.06	2,846.36	522.04	164.82	503.76	0.00	0.00	0.00
2,934.49	12.75	13.06	2,880.00	529.46	166.54	511.37	0.00	0.00	0.00
8 5/8"									
3,000.00	12.75	13.06	2,943.90	543.54	169.81	525.83	0.00	0.00	0.00
3,063.82	12.75	13.06	3,006.14	557.26	172.99	539.91	0.00	0.00	0.00
Start Drop -1.			,						
3,100.00	12.12	13.06	3,041.47	564.85	174.75	547.70	1.75	-1.75	0.00
3,200.00	10.37	13.06	3,139.55	583.84	179.16	567.20	1.75	-1.75	0.00
3,300.00	8.62	13.06	3,238.18	599.90	182.88	583.69	1.75	-1.75	0.00
3,400.00	6.87	13.06	3,337.26	613.03	185.93	597.16	1.75	-1.75	0.00
3,500.00	5.12	13.06	3,436.71	623.19	188.29	607.60	1.75	-1.75 -1.75	0.00
3,600.00	3.37	13.06	3,536.43	630.40	189.96	614.99	1.75	-1.75	0.00
3,700.00	1.62	13.06	3,636.34	634.63	190.94	619.34	1.75	-1.75	0.00
3,792.39	0.00	0.00	3,728.72	635.90	191.24	620.64	1.75	-1.75	0.00
		MD							



SDI Planning Report



Database: EDM5000-RobertS-Local

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22C PAD

 Well:
 NBU 921-22C1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Site NBU 921-22C PAD

GL 4823 & KB 4 @ 4827.00ft (ASSUMED) GL 4823 & KB 4 @ 4827.00ft (ASSUMED)

True

Jesign:	FLAN#IFKE	LIMINAL I							
Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
3,800.00	0.00	0.00	3,736.32	635.90	191.24	620.64	0.00	0.00	0.00
3,900.00	0.00	0.00	3,836.32	635.90	191.24	620.64	0.00	0.00	0.00
4,000.00	0.00	0.00	3,936.32	635.90	191.24	620.64	0.00	0.00	0.00
			4,036.32		191.24	620.64			
4,100.00	0.00	0.00		635.90			0.00	0.00	0.00
4,200.00	0.00	0.00	4,136.32	635.90	191.24	620.64	0.00	0.00	0.00
4,300.00	0.00	0.00	4,236.32	635.90	191.24	620.64	0.00	0.00	0.00
4,400.00	0.00	0.00	4,336.32	635.90	191.24	620.64	0.00	0.00	0.00
4,500.00	0.00	0.00	4,436.32	635.90	191.24	620.64	0.00	0.00	0.00
4,600.00	0.00	0.00	4,536.32	635.90	191.24	620.64	0.00	0.00	0.00
4,700.00	0.00	0.00	4,636.32	635.90	191.24	620.64	0.00	0.00	0.00
4 000 00	0.00	0.00	4 706 00	635.00	101.04	620.64	0.00	0.00	0.00
4,800.00	0.00	0.00	4,736.32	635.90	191.24	620.64	0.00	0.00	
4,900.00	0.00	0.00	4,836.32	635.90	191.24	620.64	0.00	0.00	0.00
5,000.00	0.00	0.00	4,936.32	635.90	191.24	620.64	0.00	0.00	0.00
5,038.68	0.00	0.00	4,975.00	635.90	191.24	620.64	0.00	0.00	0.00
WASATCH									
5,100.00	0.00	0.00	5,036.32	635.90	191.24	620.64	0.00	0.00	0.00
			,						
5,200.00	0.00	0.00	5,136.32	635.90	191.24	620.64	0.00	0.00	0.00
5,300.00	0.00	0.00	5,236.32	635.90	191.24	620.64	0.00	0.00	0.00
5,400.00	0.00	0.00	5,336.32	635.90	191.24	620.64	0.00	0.00	0.00
5,500.00	0.00	0.00	5,436.32	635.90	191.24	620.64	0.00	0.00	0.00
5,600.00	0.00	0.00	5,536.32	635.90	191.24	620.64	0.00	0.00	0.00
5,000.00	0.00	0.00	5,550.52	033.90	191.24	020.04	0.00	0.00	0.00
5,700.00	0.00	0.00	5,636.32	635.90	191.24	620.64	0.00	0.00	0.00
5,800.00	0.00	0.00	5,736.32	635.90	191.24	620.64	0.00	0.00	0.00
5,900.00	0.00	0.00	5,836.32	635.90	191.24	620.64	0.00	0.00	0.00
			,						
6,000.00	0.00	0.00	5,936.32	635.90	191.24	620.64	0.00	0.00	0.00
6,100.00	0.00	0.00	6,036.32	635.90	191.24	620.64	0.00	0.00	0.00
6,200.00	0.00	0.00	6,136.32	635.90	191.24	620.64	0.00	0.00	0.00
6,300.00	0.00	0.00	6,236.32	635.90	191.24	620.64	0.00	0.00	0.00
	0.00		6,336.32			620.64	0.00	0.00	0.00
6,400.00		0.00	,	635.90	191.24				
6,500.00	0.00	0.00	6,436.32	635.90	191.24	620.64	0.00	0.00	0.00
6,600.00	0.00	0.00	6,536.32	635.90	191.24	620.64	0.00	0.00	0.00
6,700.00	0.00	0.00	6,636.32	635.90	191.24	620.64	0.00	0.00	0.00
,	0.00		6,736.32		191.24	620.64		0.00	
6,800.00		0.00	,	635.90			0.00		0.00
6,900.00	0.00	0.00	6,836.32	635.90	191.24	620.64	0.00	0.00	0.00
7,000.00	0.00	0.00	6,936.32	635.90	191.24	620.64	0.00	0.00	0.00
7,100.00	0.00	0.00	7,036.32	635.90	191.24	620.64	0.00	0.00	0.00
7.200.00	0.00	0.00	7,136.32	635.90	191.24	620.64	0.00	0.00	0.00
,			,						
7,300.00	0.00	0.00	7,236.32	635.90	191.24	620.64	0.00	0.00	0.00
7,400.00	0.00	0.00	7,336.32	635.90	191.24	620.64	0.00	0.00	0.00
7,500.00	0.00	0.00	7,436.32	635.90	191.24	620.64	0.00	0.00	0.00
7,600.00	0.00	0.00	7,536.32	635.90	191.24	620.64	0.00	0.00	0.00
7,700.00	0.00	0.00	7,636.32	635.90	191.24	620.64	0.00	0.00	0.00
,			,						
7,800.00	0.00	0.00	7,736.32	635.90	191.24	620.64	0.00	0.00	0.00
7,900.00	0.00	0.00	7,836.32	635.90	191.24	620.64	0.00	0.00	0.00
7,981.68	0.00	0.00	7,918.00	635.90	191.24	620.64	0.00	0.00	0.00
MESAVERDE									
8,000.00	0.00	0.00	7,936.32	635.90	191.24	620.64	0.00	0.00	0.00
0.400.00	0.00	0.00	0.026.20	625.00	404.04	600.04	0.00	0.00	0.00
8,100.00	0.00	0.00	8,036.32	635.90	191.24	620.64	0.00	0.00	0.00
8,200.00	0.00	0.00	8,136.32	635.90	191.24	620.64	0.00	0.00	0.00
8,300.00	0.00	0.00	8,236.32	635.90	191.24	620.64	0.00	0.00	0.00
8,400.00	0.00	0.00	8,336.32	635.90	191.24	620.64	0.00	0.00	0.00
8,500.00	0.00	0.00	8,436.32	635.90	191.24	620.64	0.00	0.00	0.00
			,						
8,600.00	0.00	0.00	8,536.32	635.90	191.24	620.64	0.00	0.00	0.00
8,700.00	0.00	0.00	8,636.32	635.90	191.24	620.64	0.00	0.00	0.00



SDIPlanning Report



Database: Company: Project: EDM5000-RobertS-Local

US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22C PAD

 Well:
 NBU 921-22C1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Site NBU 921-22C PAD

GL 4823 & KB 4 @ 4827.00ft (ASSUMED) GL 4823 & KB 4 @ 4827.00ft (ASSUMED)

True

8,900.00 0.00 0.00 0.00 8,836.32 635.90 191.24 620.64 0.00 0.00 0.00 9,000.00 9,000.00 0.00 0	ned Survey									
8,900.00	Depth			Depth			Section	Rate	Rate	Rate
9,200.00 0.00 0.00 9,136.32 635.90 191.24 620.64 0.00 0.00 0.00 9,300.00 0.00 0.00 0.00 9,336.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,500.00 0.00 0.00 0.00 9,336.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,500.00 0.00 0.00 9,436.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,500.00 0.00 0.00 9,436.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,700.00 0.00 0.00 9,536.32 635.90 191.24 620.64 0.00 0.00 0.00 9,700.00 0.00 0.00 9,336.32 635.90 191.24 620.64 0.00 0.00 0.00 9,800.00 0.00 0.00 9,336.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,800.00 0.00 0.00 9,336.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,900.00 0.00 0.00	8,900.00	0.00	0.00	8,836.32	635.90	191.24	620.64	0.00	0.00	0.00 0.00 0.00
9,700.00 0.00 0.00 9,636.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 9,800.00 0.00 0.00 0.00 9,736.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,000.00 0.00 0.00	9,200.00 9,300.00 9,400.00	0.00 0.00 0.00	0.00 0.00 0.00	9,136.32 9,236.32 9,336.32	635.90 635.90 635.90	191.24 191.24 191.24	620.64 620.64 620.64	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00
10,199.68	9,700.00 9,800.00 9,900.00	0.00 0.00 0.00	0.00 0.00 0.00	9,636.32 9,736.32 9,836.32	635.90 635.90 635.90	191.24 191.24 191.24	620.64 620.64 620.64	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00
10,200.00 0.00 0.00 10,136.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,262.68 0.00 0.00 10,199.00 635.90 191.24 620.64 0.00 0.00 0.00 0.00 0.00 0.00 0.00	10,199.68									0.00 0.00
10,300.00 0.00 0.00 10,236.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,400.00 0.00 10,336.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,500.00 0.00 10,436.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,600.00 0.00 10,536.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,658.68 0.00 0.00 10,595.00 635.90 191.24 620.64 0.00 0.00 0.00 0.00 0.00 0.00 0.00	10,200.00 10,262.68	0.00								0.00 0.00
10,400.00			0.00	10 006 00	625.00	101.04	620.64	0.00	0.00	0.00
10,700.00 0.00 0.00 10,636.32 635.90 191.24 620.64 0.00 0.00 0.00 10,800.00 0.00 0.00 10,736.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 10,900.00 0.00 0.00 10,836.32 635.90 191.24 620.64 0.00 0.00 0.00 0.00 11,000.00 0.00 0.00 10,936.32 635.90 191.24 620.64 0.00 0.00 0.00 11,100.00 0.00 0.00 11,036.32 635.90 191.24 620.64 0.00 0.00 0.00	10,400.00 10,500.00 10,600.00 10,658.68	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	10,336.32 10,436.32 10,536.32 10,595.00	635.90 635.90 635.90	191.24 191.24 191.24	620.64 620.64 620.64	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00 0.00
10,800.00 0.00 0.00 10,736.32 635.90 191.24 620.64 0.00 0.00 0.00 10,900.00 0.00 0.00 10,836.32 635.90 191.24 620.64 0.00 0.00 0.00 11,000.00 0.00 0.00 10,936.32 635.90 191.24 620.64 0.00 0.00 0.00 11,100.00 0.00 0.00 11,036.32 635.90 191.24 620.64 0.00 0.00 0.00			_		625.00	101 24	620.64	0.00	0.00	0.00
,	10,800.00 10,900.00 11,000.00 11,100.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	10,736.32 10,836.32 10,936.32 11,036.32	635.90 635.90 635.90 635.90	191.24 191.24 191.24 191.24	620.64 620.64 620.64 620.64	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
11,258.68 0.00 0.00 11,195.00 635.90 191.24 620.64 0.00 0.00 0.00										0.00

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
BLACKHAWK_NBU 921 - plan hits target cent - Circle (radius 25.00)		0.00	10,595.00	635.90	191.24	14,539,821.58	2,049,435.51	40° 1' 43.043 N	109° 32' 20.184 W
PBHL_NBU 921-22C1B: - plan hits target cent - Circle (radius 100.0		0.00	11,195.00	635.90	191.24	14,539,821.58	2,049,435.51	40° 1' 43.043 N	109° 32' 20.184 W



SDIPlanning Report



Database: EDM5000-RobertS-Local Company: US ROCKIES REGION P

US ROCKIES REGION PLANNING UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 921-22C PAD

 Well:
 NBU 921-22C1BS

Wellbore: OH

Project:

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Site NBU 921-22C PAD

GL 4823 & KB 4 @ 4827.00ft (ASSUMED) GL 4823 & KB 4 @ 4827.00ft (ASSUMED)

True

Casing Points					
	Measured	Vertical		Casing	Hole
	Depth	Depth		Diameter	Diameter
	(ft)	(ft)	Name	(in)	(in)
	2.934.49	2.880.00 8 5/8"		8.625	11.000

Formations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,568.82	1,548.00	GREEN RIVER				
	1,920.49	1,891.00	BIRDSNEST				
	2,473.11	2,430.00	MAHOGANY				
	5,038.68	4,975.00	WASATCH				
	7,981.68	7,918.00	MESAVERDE				
	10,199.68	10,136.00	SEGO				
	10,262.68	10,199.00	CASTLEGATE				
	10,658.68	10,595.00	BLACKHAWK				

Plan Annotations				
Measured	Vertical	Local Coord	dinates	
Depth (ft)	Depth (ft)	+N/-S (ft)	+E/-W (ft)	Comment
300.00	300.00	31.32	50.96	Start Build 2.00
937.50	932.25	100.13	66.93	Start 2126.32 hold at 937.50 MD
3,063.82	3,006.14	557.26	172.99	Start Drop -1.75
3,792.39	3,728.72	635.90	191.24	Start 7466.28 hold at 3792.39 MD
11,258.68	11,195.00	635.90	191.24	TD at 11258.68

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 1 of 10

Kerr-McGee Oil & Gas Onshore, L.P.

NBU 921-22C Pad

API #	_	NBU 921-22C GR		
	Surface:	723 FNL / 1959 FWL	NENW	Lot
	BHL:	723 FNL / 1959 FWL	NENW	Lot
API#		NBU 921-22C1BS		
	Surface:	691 FNL / 2010 FWL	NENW	Lot
	BHL:	85 FNL / 2150 FWL	NENW	Lot
API#		NBU 921-22C4CS		
	Surface:	696 FNL / 2001 FWL	NENW	Lot
	BHL:	1078 FNL / 2149 FWL	NENW	Lot
<u>API #</u>		NBU 921-22F1BS		
	Surface:	701 FNL / 1993 FWL	NENW	Lot
	BHL:	1410 FNL / 2149 FWL	SENW	Lot
API#		NBU 921-22F1CS		
	Surface:	707 FNL / 1984 FWL	NENW	Lot
	BHL:	1742 FNL / 2149 FWL	SENW	Lot
API#		NBU 921-22F4BS		
	Surface:	712 FNL / 1976 FWL	NENW	Lot
	BHL:	2073 FNL / 2149 FWL	SENW	Lot

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on October 3-4, 2011. Present were:

- Bucky Secakuku (10/4/2011 only) BIA;
- · LeAllen Blackhair, Rainey Longhair Ute Indian Tribe;
- · Kelly Jo Jackson Montgomery Archeological Consultants Inc.;
- Scott Carson Smiling Lake Consulting;
- · John Slaugh, Mitch Batty Timberline Engineering & Land Surveying, Inc.;
- Laura Abrams, Charles Chase, Raleen White, Doyle Holmes, Lovel Young, Sheila Wopsock Kerr-McGee

A. Existing Roads:

Existing roads consist of county and improved/unimproved access roads (two-tracks). In accordance with Onshore Order #1, Kerr-McGee will, in accordance with BMPs, improve or maintain existing roads in a condition that is the same as or better than before operations began. New or reconstructed proposed access roads are discussed in Section B.

The existing roads will be maintained in a safe and usable condition. Maintenance for existing roads will continue until final abandonment and reclamation of well pads and/or other facilities, as applicable. Road maintenance will include, but is not limited to, blading, ditching, and/or culvert installation and cleanout. To ensure safe operating conditions, gravel surfacing will be performed where excessive rutting or erosion may occur. Dust control will be performed as necessary to ensure safe operating conditions.

Roads, gathering lines and electrical distribution lines will occupy common disturbance corridors where possible. Where available, roadways will be used as the staging area and working space for installation of gathering lines. All disturbances located in the same corridor will overlap each other to the maximum extent possible, while maintaining safe and sound construction and installation practices. Unless otherwise approved or requested in site specific documents, in no case will the maximum disturbance widths of the access road and utility corridors exceed the widths specified in Part D of this document.

Please refer to Topo B, for existing roads.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 2 of 10

B. New or Reconstructed Access Roads:

All new or reconstructed roads will be located, designed, and maintained to meet the standards of the BIA.

Each new well pad or pad expansion may require construction of a new access road and/or de-commissioning of an older road. Plans, routes, and distances for new roads and road improvements are provided in design packages, exhibits and maps for a project. Project-specific maps are submitted to depict the locations of existing, proposed, and/or decommissioned and include the locations for supporting structures, including, but not limited to, culverts, bridges, low water crossings, range infrastructure, and haul routes, as per OSO 1. Designs for cuts and fills, including spoils source and storage areas, are provided with the road designs, as necessary.

Where safety objectives can be met. As applicable, Kerr-McGee may use unimproved and/or two-track roads for lease operations, to lessen total disturbance.

Road designs will be based on the road safety requirements, traffic characteristics, environmental conditions, and the vehicles the road is intended to carry. Generally, newly constructed unpaved lease roads will be crowned and ditched with the running surfaces of the roads approximately 12-18 feet wide and a total road corridor width not to exceed 45 feet, except where noted in the road design for a specific project. Maximum grade will generally not exceed 8%. Borrow ditches will be back sloped 3:1 or less. Construction BMPs will be employed to control onsite and offsite erosion.

Where topography would direct storm water runoff to an access road or well pad, drainage ditches or other common drainage control facilities, such as V- or wing-ditches, will be constructed to divert surface water runoff. Drainage features, including culverts, will be constructed or installed prior to commencing other operations, including drilling or facilities placement. Riprap will be placed at the inlet and outlet at the culvert(s), as necessary.

Prior to construction, new access road(s) will be staked according to the requirements of OSO 1. Construction activity will not be conducted using frozen or saturated materials or during periods when significant watershed damage (e.g. rutting, extensive sheet soil erosion, formation of rills/gullies, etc.) is likely to occur. Vegetative debris will not be placed in or under fill embankments.

New road maintenance will include, but is not limited to, blading, ditching, culvert installation and cleanout, gravel surfacing where excessive rutting or erosion may occur and dust control, as necessary to ensure safe operating conditions. All vehicular traffic, personnel movement, construction/restoration operations will be confined to the approved area and to existing roadways and/or access routes.

Snow removal will be conducted on an as-needed basis to accommodate safe travel. Snow removal will occur as necessary throughout the year, as will necessary drainage ditch construction. Removed snow may be stored on permitted well pads to reduce hauling distances and/or at the aerial extent of approved disturbance boundaries to facilitate snow removal for the remainder of the season.

If a county road crossing or encroachment permit is needed, it will be obtained prior to construction.

The following segments are "on-lease"

 ± 175 ' (0.03 miles) – Section 22 T9S R21E (NW/4) – On-lease UTU0147566, road re-route from the edge of pad to the existing road to the east. Please refer to Topo B.

C. Location of Existing Wells:

A) Refer to Topo Map C.

D. Location of Existing and/or Proposed Facilities:

This pad will expand the existing pad for the NBU 192, which is a producing gas well according to Utah Division of Oil, Gas and Mining (UDOGM) records on November 3, 2011. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (Kerr-McGee).

Should the well(s) prove productive, production facilities will be installed on the disturbed portion of each well pad. A berm will be constructed completely around production components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will generally be constructed of compacted subsoil or corrugated metal, and will hold the capacity of the largest tank and have sufficient freeboard to accommodate a 25 year rainfall event. This includes pumping units. Aboveground structures constructed or installed onsite for 6 months or longer, will be painted a flat, non-reflective, earth-tone color chosen at the onsite (typically Shadow Gray). A production facility layout is provided as part of a project-specific APD, ROW or NOS submission.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 3 of 10

GAS GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

coating (or equivalent). The total gas gathering pipeline distance from the meter to the tie in point is $\pm 315^{\circ}$ and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

±315' (0.06 miles) – Section 22 T9S R21E (NW/4) – On-lease UTU0147566 Ute Indian Tribe surface, New 8" buried gas gathering pipeline from the meter to the proposed 16" gas pipeline- ROW in progress. Please refer to Topo D2 - Pad and Pipeline Detail.

LIQUID GATHERING

Please refer to Topo D2- Pad and Pipeline Detail.

The total liquid gathering pipeline distance from the separator to the tie in point is ± 315 ' and the individual segments are broken up as follows:

The following segments will require a ROW to be submitted under a different cover to the Ute Indian Tribe.

 ± 315 ' (0.06 miles) – Section 22 T9S R21E (NW/4) – On-lease UTU0147566 Ute Indian Tribe surface, New 6" buried liquid gathering pipeline from the separator to the proposed 6" liquid pipeline- ROW in progress. Please refer to Topo D2 - Pad and Pipeline Detail.

Pipeline Gathering Construction

Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee. Gas gathering pipeline(s,) gas lift, or liquids pipelines may be constructed to lie on the surface or be buried. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. The area of disturbance during construction from the edge of road or well pad will typically be 30' in width. Where pipelines run cross country, the width of disturbance will typically be 45 ft for buried lines and 30 ft for surface lines. In addition, Kerr-McGee requests for a permanent 30' disturbance width that will be maintained for the portion adjacent to the road. The need for the 30' permanent disturbance width is for maintenance and repairs. Cross country permanent disturbance width also are required to be 30ft.

Above-ground installation will generally not require clearing of vegetation or blading of the surface, except where safety considerations necessitate earthwork. In some surface pipeline installation instances pipe cannot be constructed where it will lay. In these cases where an above-ground pipeline is constructed parallel and adjacent to a road, it will be welded/fused on the road and then lifted from the road to the pipeline route. In other cases where a pipeline route is not parallel and adjacent to a road (cross-country between sites), it will be welded/fused in place at a well pad, access road, or designated work area and pulled between connection locations with a suitable piece of equipment.

Buried pipelines will generally be installed parallel and adjacent to existing and/or newly constructed roads and within the permitted disturbance corridor. Buried pipelines may vary from 2 inches (typically fuel gas lines) to 24 inches (typically transportation lines) in diameter, but 6 to 16 inches is typical for a buried gas line. The diameter of liquids pipelines may vary from 2 inches to 12 inches, but 6 inches is the typical diameter. Gas lift lines may vary from 2 to 12 inches in diameter, but 6-inch diameter pipes are generally used for gas lift. If two or more pipelines are present (gas gathering, gas lift, and fluids), they will share a common trench where possible.

Typically, to install a buried pipeline, topsoil will be removed, windrowed and placed on the non-working side of the route for later reclamation. Because working room is limited, the spoil may be spread out across the working side and construction will take place on the spoil. The working side of the corridor will be used for pipe stringing, bending, welding and equipment travel. Small areas on the working side displaying ruts or uneven ground will be groomed to facilitate the safe passage of equipment. After the pipelines are installed, spoil will be placed back into the trench, and the topsoil will be redistributed over the disturbed corridor prior to final reclamation. Typical depth of the trench will be 6 feet, but depths may vary according to site-specific conditions (presence of bedrock, etc.). The proposed trench width for the pipeline would range from 18-48 inches.

The pipeline will be welded along the proposed route and lowered into place. Trenching equipment will cut through the soil or into the bedrock and create good backfill, eliminating the need to remove large rocks. The proposed buried pipeline will be visually and radiographically inspected and the entire pipeline will be pneumatically or hydrostatically tested before being placed into service. Routine vehicle traffic will be prevented from using pipeline routes as travel ways by posting signs at the route's intersection with an access road.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 4 of 10

If pipelines or roads encounter a drainage that could be subject to flooding or surface water during extreme precipitation events, Kerr-McGee will apply all applicable Army Corps mandates as well as the BLM's Hydraulic Considerations for Pipeline Crossings of Stream Channels (BLM Technical Note 423, April 2007). In addition, all stream and drainage crossings will be evaluated to determine the need for stream alteration permits from the State of Utah Division of Water Rights and if necessary, required permits will be secured. Similarly, where a road or pipeline crossing exists the pipe will be butt welded and buried to a depth between 24 and 48 inches or more. Dirt roads will be cut and restored to a condition equivalent to the existing condition. All Uintah County road encroachment and crossing permits, where applicable, will be obtained prior to crossing construction. In no case will pressure testing of pipelines result in discharge of liquids to the surface.

Pipeline signs will be installed along the route to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations for production integrity and safety purposes.

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to section J for more details regarding final reclamation.

When no longer deemed necessary by the operator, Kerr-McGee or it's successor will consult with the Vernal BIA Office before terminating of the use of the pipeline(s).

The Anadarko Completions Transportation System (ACTS) information:

Kerr-McGee will use either a closed loop drilling system that will require one pit and one storage area to be constructed on the drilling pad or a traditional drilling operation with one pit. The storage area will be used to contain only the de-watered drill cuttings and will be lined and reclaimed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion operations pit is lined and will be used for the wells drilled on the pad or used as part of our Anadarko Completions Transportation (ACTS) system which is discussed in more detail below. Using the closed loop drilling system will allow Kerr-McGee to decrease the amount of disturbance/footprint on location compared to a single large drilling/completion pit.

If Kerr-McGee does not use a closed loop system, it will construct a drilling reserve pit to contain drill cuttings and for use in completion operations. Depending on the location of the pit, its relation to future drilling locations, the reserve/completion pit will be utilized for the completion of the wells on that pad and/or be used as part of our ACTS system.

Kerr-McGee will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of frac fluids by utilizing existing reserve pits and temporary, surface-laid aluminum liquids transfer lines between frac locations. The pit will be refurbished as follows when a traditional drill pit is used: mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. Kerr-McGee will reline the pit with a 30 mil liner and double felt padding. The refurbished pit will be the same size or smaller as specified in the originally approved ROW/APD. The pit refurb will be done in a normal procedure and there will be no modification to the pit.

All four sides of the completions pit will be fenced in according to standard pit fencing procedures. Netting will be installed over all pits.

The collected hydrocarbons will be treated and sold at approved sales facilities. A loading rack with drip containment will also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit.

ACTS will require temporarily laying multiple 6" aluminum water transfer lines on the surface between either existing or refurbished reserve pits. The temporary aluminum transfer lines will be utilized to transport frac fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads or pipeline corridors. Upon completion of the frac operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The temporary ACTS lines will be permitted under a separate cover to the Ute Indian Tribe.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig. Kerr-McGee requests to keep the netted pit open for one year from first production of the first produced well on the pad. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other frac jobs in the area. After one year Kerr-McGee will backfill the pit and reclaim. If the pit is not needed for an entire year it will be backfilled and reclaimed earlier. Kerr-McGee understands that due to the temporary nature of this system, BIA considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BIA.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 5 of 10

E. Location and Types of Water Supply:

Water for drilling and completion operations will be obtained from the following sources:

Permit # 49-2307	JD Field Services	Green River- Section 15, T2N, R22E
Permit # 49-2321	R.N. Industries	White River- Section 2, T10S, R24E
Permit # 49-2319	R.N. Industries	White River- Various Sources
Permit # 49-2320	R.N. Industries	Green River- Section 33, T8S, R23E

Water will be hauled to location over the roads marked on Maps A and B.

No water well is to be drilled on this lease.

F. Construction Materials:

Construction operations will typically be completed with native materials found on location. Construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source (described in site-specific documents). No construction materials will be removed from Tribal lands without prior approval from the BIA. A source location other than an on-location construction site will be designated either via a map or narrative within the project specific materials provided to the BIA.

G. Methods for Handling Waste:

All wastes subject to regulation will be handled in compliance with applicable laws to minimize the potential for leaks or spills to the environment. Kerr-McGee also maintains a Spill Control and Countermeasure Plan, which includes notification requirements, including the BIA, for all reportable spills of oil, produced liquids, and hazardous materials.

Any accidental release, such as a leak or spill in excess of the reportable quantity, as established by 40 CFR Part 117.3, will be reported as per the requirements of CERCLA, Section 102 B. If a release involves petroleum hydrocarbons or produced liquids, Kerr-McGee will comply with the notification requirements of NTL-3A. Drill cuttings and/or drilling fluids will be contained in the reserve/frac pit whether a closed loop system is used or not. Cuttings will be buried in pit(s) upon closure. Unless specifically approved by the BIA, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface precipitation runoff into the pit (via appropriate placement of subsoil storage areas and/or construction of berms, ditches, etc.). Should unexpected liquid petroleum hydrocarbons (crude oil or condensate) be encountered during drilling, completions or well testing, liquid petroleum hydrocarbons will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by the BIA. Should timely removal not be feasible, the pit will be netted as soon as practical. Similarly, hydrocarbon removal will take place prior to the closure of the pit, unless authorization is provided for disposal via alternate pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with an impermeable liner. The liner will be a synthetic material 30 mil or thicker. The bottom and side walls of the pit will be void of any sharp rocks that could puncture the liner. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. After evaporation and when dry, the reserve pit liners will be cut off, ripped and/or folded back (as safety considerations allow) as near to the mud surface as possible and buried on location or hauled to a landfill prior to backfilling the pit with a minimum of five feet of soil material.

Where necessary and if conditions (freeboard, etc.) allow, produced liquids from newly completed wells may be temporarily disposed of into pits for a period not to exceed 90 days as per Onshore Order Number 7 (OSO 7). Subsequently, permanent approved produced water disposal methods will be employed in accordance with OSO 7 and/or as described in a Water Management Plan (WMP). Otherwise, fluids disposal locations and associated haul routes, for ROW consideration, are typically depicted on Topo A of individual projects. Revisions to the water source or method of transportation will be subject to written approval from the BIA.

Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after one year from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse (trash and other solid waste including cans, paper, cable, etc.) generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility. Immediately after removal of the drilling rig, all debris and other waste materials not contained within trash receptacles will be collected and removed from the well location.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 6 of 10

For the protection of livestock and wildlife, all open pits (excluding flare pits) will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet. Siphons, catchments, and absorbent pads will be installed to keep hydrocarbons produced by the drilling rig or other equipment on location from entering the reserve pit. Hydrocarbons, contaminated pads, and/or soils will be disposed of in accordance with state and federal requirements.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Hazardous materials may be contained in some grease or lubricants, solvents, acids, paint, and herbicides, among others as defined above. Kerr-McGee maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances that are used during the course of construction, drilling, completion, and production operations for this project. The transport, use, storage and handling of hazardous materials will follow procedures specified by federal and state regulations. Transportation of hazardous materials to the well location is regulated by the Department of Transportation (DOT) under 49 CFR, Parts 171-180. DOT regulations pertain to the packing, container handling, labeling, vehicle placarding, and other safety aspects.

Potentially hazardous materials used in the development or operation of wells will be kept in limited quantities on well sites and at the production facilities for short periods of time. Chemicals meeting the criteria for being an acutely hazardous material/substance or meet the quantities criteria per BLM Instruction Memorandum No. 93-344 will not be used.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities (crude oil/condensate, produced water). They may also be kept in limited quantities on drilling sites (barite, diesel fuel, cement, cottonseed hulls etc.) for short periods of time during drilling or completion activities.

Fluids disposal and pipeline/haul routes are depicted on Topo Map A.

Any produced water separated from recoverable condensate from the proposed well will be contained in a water tank and will then be transported by pipeline and/or truck to one of the pre-approved disposal sites:

RNI in Sec. 5 T9S R22E NBU #159 in Sec. 35 T9S R21E Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following Kerr-McGee active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 34 T9S R21E

H. Ancillary Facilities:

ancillary facilities are

I. Well Site Layout:

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit (for closed loop or non-closed loop operations), access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment depending on whether a closed loop system is used. Surface distance may be less if using closed loop. But in either case, the area of disturbance will not exceed the maximum disturbance outlined in the attached exhibits.

RECEIVED: April 20, 2012

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Opshore J. P. NBU 921-22C Pad Surface Use Plan of Operations 7 of 10

For the protection of livestock and wildlife, all open pits and cellars will be fenced to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Each well will utilize either a centralized tank battery, centralized fluids management system, or have tanks installed on its pad. Production/ Produced Liquid tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks will be kept reasonably free from surface accumulations of liquid hydrocarbons. The tanks are not to be used for disposal of liquids from additional sources without prior approval of BIA.

J. Plans for Surface Reclamation:

The surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. Interim reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation may include pit evaporation, fluid removal, pit solidification, re-contouring, ripping, spreading top soil, seeding, and/or weed control. Interim reclamation will be performed in accordance with OSO 1, or written notification will be provided to the BIA for approval. Where feasible, drilling locations, reserve pits, or access routes not utilized for production operations will be re-contoured to a natural appearance.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit. Disposal of pit fluids and linings is discussed in Section G.

Final Reclamation

Final reclamation will be performed for unproductive wells and after the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by Kerr-McGee. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. The BIA will be notified prior to commencement of reclamation operations. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring the site to the approximate contour that existed prior to pad construction, final grading will be conducted over the entire surface of the well site and access road. The area will be ripped to a depth of 18 to 24 inches on 18 to 24 inch centers, where practical. The surface soil material will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep, where practical. The entire area will be uniformly covered with the depressions constructed perpendicular to the natural flow of water.

Reclamation of roads will be performed at the discretion of the BIA/Tribe. All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded in accordance with the seeding specifications as proposed below in "Measures Common to Interim and Final Reclamation".

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to the BIA/Tribe.

Measures Common to Interim and Final Reclamation

Soil preparation will be conducted using a disk for areas in need of more soil preparation following site preparation. This will provide primary soil tillage to a depth no greater than 6 inches. Prior to reseeding, compacted areas will be scarified by ripping or chiseling to loosen compacted soils, promote water infiltration, and improve soil aeration and root penetration.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore. L.P. NBU 921-22C Pad Surface Use Plan of Operations 8 of 10

Seeding will occur year-round as conditions allow and will typically be accomplished through the use of a no-till rangeland style seed drill with a "picker box" in order to seed "fluffy" seed. Where drill seeding is not the preferred method, seed will be broadcast and then raked into the ground at double the rate of drill seeding. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for re-vegetation. The seed mixes will be selected from a list provided by or approved by the BIA/Tribe or a specific seed mix will be proposed by Kerr-McGee to the BIA/Tribe and used after its approval. The selected specific seed mix for each well location and road segment will be utilized while performing interim and final reclamation for each project. All seed will be certified and tags will be maintained by Kerr-McGee. Every effort will be made to obtain "cheat grass free seed".

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

Indian Ricegrass (Nezpar)	3
Sandberg Bluegrass	0.75
Bottlebrush Squirreltail	1
Great Basin Wildrye	0.5
Crested Wheatgrass	1.5
Winterfat	0.25
Shadscale	1.5
Four-wing Saltbrush	0.75
Forage Kochia	0.25
Total	9.5

Additional soil amendments and/or stabilization may be required on sites with poor soils and/or excessive erosion potential. Where severe erosion can become a problem and/or the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. Slopes will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to: erosion control blankets, hydro-mulch, and/or bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Weed Control

Noxious weeds will be controlled in akk orihect areas un accordance with all applicable rules and regulations.

$\textbf{K.} \quad \textbf{Surface/Mineral Ownership:} \\$

 Ute Indian Tribe
 United States of America

 P.O. Box 70
 Bureau of Land Management

 988 South 7500 East Annex Building
 170 South 500 East

 Fort Duschesne, UT 84026
 Vernal, UT 84078

 (435) 722-4307
 (435)781-4400

L. Other Information:

Onsite Specifics:

- Proposed pond on west side of the pad will be added to alteration permit
- Arch monitor during construction
- Paleo monitor during construction

Cultural and Paleontological Resources

All personnel are strictly prohibited from collecting artifacts, any paleontological specimens or fossils, and from disturbing any significant cultural resources in the area. If artifacts, fossils, or any culturally sensitive materials are exposed or identified in the area of construction, all construction operations that would affect the newly discovered resource will cease, and Kerr-McGee will provide immediate notification to the BIA.

Resource Reports

A Class I literature survey was completed in December 2011 by Montgomery Archaeological Consultants, Inc. (MOAC). For additional details please refer to report MOAC 11-406.

A paleontological reconnaissance survey was completed on July 20, 2010 by SWCA Environmental Consultants. For additional details please refer to report UT11-14314-115.

Biological field survey was completed on August 8 and 16, 2011 by Grasslands Consulting, Inc (GCI). For additional details please refer to report GCI-566.

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore, L.P. NBU 921-22C Pad Surface Use Plan of Operations 9 of 10

Proposed Action Annual Emissions Tables:

Table 1: Proposed Action Annual Emissions (tons/year) ¹						
Pollutant	Development	Production	Total			
NOx	3.8	0.12	3.92			
CO	2.2	0.11	2.31			
VOC	0.1	4.9	5			
SO_2	0.005	0.0043	0.0093			
PM_{10}	1.7	0.11	1.81			
PM _{2.5}	0.4	0.025	0.425			
Benzene	2.2E-03	0.044	0.046			
Toluene	1.6E-03	0.103	0.105			
Ethylbenzene	3.4E-04	0.005	0.005			
Xylene	1.1E-03	0.076	0.077			
n-Hexane	1.7E-04	0.145	0.145			
Formaldehyde	1.3E-02	8.64E-05	1.31E-02			

¹ Emissions include 1 producing well and associated operations traffic during the year in

which the project is developed

Table 2:	Proposed Action versus 201 Inventory Com		I Emissions
Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	23.52	16,547	0.14%
VOC	30	127,495	0.02%

a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Uintah Basin Data

NBU 921-22C GR/ 921-22C1BS/ 921-22C4CS NBU 921-22F1BS/ 921-22F1CS/ 921-22F4BS Kerr-McGee Oil Gas Onshore, L.P.

NBU 921-22C Pad Surface Use Plan of Operations 10 of 10

M. Lessee's or Operators' Representative & Certification:

Laura Abrams Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6356

Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

December 15, 2011

Laura Abrams

Date



Kerr-McGee Oil & Gas Onshore LP PO Box 173779 DENVER, CO 80217-3779

October 10, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 921-22C1BS

T9S-R21E

Section 22 NENW (Surface and Bottom Hole)

Surface: 691' FNL, 2010' FWL Bottom Hole: 85' FNL, 2150' FWL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling.

- Kerr-McGee's NBU 921-22C1BS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing roads and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.


Therefore, based on the above stated information, Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Joe Matney Sr. Staff Landman

Joe Matiney



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office P.O. Box 45155 Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

May 14, 2012

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2012 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2012 within the Natural Buttes Unit, Uintah County, Utah.

BHL Sec 22 T09S R21E 0579 FNL 1819 FEL

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

WELL PAD - NBU 921-22K 43-047-52550 NBU 921-22K2AS Sec 22 T09S R21E 1748 FSL 1611 FWL BHL Sec 22 T09S R21E 2366 FSL 1832 FWL 43-047-52551 NBU 921-22K4CS Sec 22 T09S R21E 1753 FSL 1640 FWL BHL Sec 22 T09S R21E 1576 FSL 2147 FWL 43-047-52552 NBU 921-22N1BS Sec 22 T09S R21E 1751 FSL 1630 FWL BHL Sec 22 T09S R21E 1244 FSL 2147 FWL 43-047-52575 NBU 921-22F4CS Sec 22 T09S R21E 1755 FSL 1650 FWL BHL Sec 22 T09S R21E 2406 FNL 2148 FWL 43-047-52576 NBU 921-22F3DS Sec 22 T09S R21E 1747 FSL 1601 FWL BHL Sec 22 T09S R21E 2634 FNL 1870 FWL 43-047-52580 NBU 921-22N1CS Sec 22 T09S R21E 1750 FSL 1620 FWL BHL Sec 22 T09S R21E 0912 FSL 2146 FWL WELL PAD - NBU 921-22B 43-047-52553 NBU 921-22G1CS Sec 22 T09S R21E 0973 FNL 1861 FEL BHL Sec 22 T09S R21E 1574 FNL 1818 FEL 43-047-52554 NBU 921-22B4CS Sec 22 T09S R21E 0965 FNL 1854 FEL BHL Sec 22 T09S R21E 1243 FNL 1819 FEL 43-047-52555 NBU 921-22B4BS Sec 22 T09S R21E 0935 FNL 1828 FEL BHL Sec 22 T09S R21E 0911 FNL 1819 FEL 43-047-52556 NBU 921-22B1CS Sec 22 T09S R21E 0950 FNL 1841 FEL

RECEIVED: May 15, 2012

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

43-047-52557 NBU 921-22B1BS Sec 22 T09S R21E 0958 FNL 1848 FEL

BHL Sec 22 T09S R21E 0249 FNL 1819 FEL

43-047-52607 NBU 921-22A1S Sec 22 T09S R21E 0943 FNL 1835 FEL

BHL Sec 22 T09S R21E 0386 FNL 0464 FEL

WELL PAD - NBU 921-22C

43-047-52558 NBU 921-22C1BS Sec 22 T09S R21E 0691 FNL 2010 FWL

BHL Sec 22 T09S R21E 0085 FNL 2150 FWL

43-047-52567 NBU 921-22C4CS Sec 22 T09S R21E 0696 FNL 2001 FWL

BHL Sec 22 T09S R21E 1078 FNL 2149 FWL

43-047-52569 NBU 921-22F1BS Sec 22 T09S R21E 0701 FNL 1993 FWL

BHL Sec 22 T09S R21E 1410 FNL 2149 FWL

43-047-52570 NBU 921-22F1CS Sec 22 T09S R21E 0707 FNL 1984 FWL

BHL Sec 22 T09S R21E 1742 FNL 2149 FWL

43-047-52571 NBU 921-22F4BS Sec 22 T09S R21E 0712 FNL 1976 FWL

BHL Sec 22 T09S R21E 2073 FNL 2149 FWL

WELL PAD - NBU 921-22I

43-047-52560 NBU 921-22I1CS Sec 22 T09S R21E 1973 FSL 0620 FEL

BHL Sec 22 T09S R21E 2237 FSL 0494 FEL

43-047-52561 NBU 921-22I1BS Sec 22 T09S R21E 1981 FSL 0626 FEL

BHL Sec 22 T09S R21E 2569 FSL 0494 FEL

43-047-52562 NBU 921-22G4CS Sec 22 T09S R21E 2013 FSL 0650 FEL

BHL Sec 22 T09S R21E 2569 FNL 1818 FEL

43-047-52564 NBU 921-22J4CS Sec 22 T09S R21E 1989 FSL 0632 FEL

BHL Sec 22 T09S R21E 1410 FSL 1817 FEL

43-047-52565 NBU 921-22J4AS Sec 22 T09S R21E 1997 FSL 0638 FEL

BHL Sec 22 T09S R21E 1796 FSL 1580 FEL

43-047-52566 NBU 921-22J1BS Sec 22 T09S R21E 2005 FSL 0644 FEL

BHL Sec 22 T09S R21E 2405 FSL 1817 FEL

WELL PAD - NBU 921-22H

43-047-52563 NBU 921-22H4CS Sec 22 T09S R21E 2196 FNL 0627 FEL

BHL Sec 22 T09S R21E 2403 FNL 0494 FEL

43-047-52650 NBU 921-22H1CS Sec 22 T09S R21E 2179 FNL 0637 FEL

BHL Sec 22 T09S R21E 1740 FNL 0494 FEL

43-047-52651 NBU 921-22A4CS Sec 22 T09S R21E 2170 FNL 0642 FEL

BHL Sec 22 T09S R21E 1288 FNL 0504 FEL

43-047-52652 NBU 921-22A4BS Sec 22 T09S R21E 2162 FNL 0647 FEL

BHL Sec 22 T09S R21E 0670 FNL 0494 FEL

43-047-52653 NBU 921-22H4BS Sec 22 T09S R21E 2188 FNL 0632 FEL

BHL Sec 22 T09S R21E 2071 FNL 0494 FEL

Page 2

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

WELL PAD - NBU 921-22E

43-047-52568 NBU 921-22E4BS Sec 22 T09S R21E 2179 FNL 0750 FWL

BHL Sec 22 T09S R21E 2239 FNL 0824 FWL

43-047-52572 NBU 921-22E1BS Sec 22 T09S R21E 2179 FNL 0720 FWL

BHL Sec 22 T09S R21E 1576 FNL 0824 FWL

43-047-52573 NBU 921-22E1CS Sec 22 T09S R21E 2179 FNL 0730 FWL

BHL Sec 22 T09S R21E 1908 FNL 0824 FWL

43-047-52574 NBU 921-22E4CS Sec 22 T09S R21E 2179 FNL 0740 FWL

BHL Sec 22 T09S R21E 2572 FNL 0824 FWL

WELL PAD - NBU 921-22L

43-047-52577 NBU 921-22K2DS Sec 22 T09S R21E 1668 FSL 0666 FWL

BHL Sec 22 T09S R21E 2038 FSL 1784 FWL

43-047-52582 NBU 921-22L1BS Sec 22 T09S R21E 1660 FSL 0648 FWL

BHL Sec 22 T09S R21E 2408 FSL 0824 FWL

43-047-52583 NBU 921-22L4BS Sec 22 T09S R21E 1672 FSL 0675 FWL

BHL Sec 22 T09S R21E 1744 FSL 0824 FWL

43-047-52585 NBU 921-22L1CS Sec 22 T09S R21E 1664 FSL 0657 FWL

BHL Sec 22 T09S R21E 2076 FSL 0824 FWL

WELL PAD - NBU 921-220

43-047-52578 NBU 921-2204CS Sec 22 T09S R21E 0269 FSL 1655 FEL

BHL Sec 22 T09S R21E 0086 FSL 1816 FEL

43-047-52579 NBU 921-22P4BS Sec 22 T09S R21E 0280 FSL 1606 FEL

BHL Sec 22 T09S R21E 0581 FSL 0494 FEL

43-047-52581 NBU 921-22P4CS Sec 22 T09S R21E 0278 FSL 1616 FEL

BHL Sec 22 T09S R21E 0251 FSL 0494 FEL

43-047-52590 NBU 921-2204BS Sec 22 T09S R21E 0271 FSL 1645 FEL

BHL Sec 22 T09S R21E 0416 FSL 1816 FEL

43-047-52612 NBU 921-2201BS Sec 22 T09S R21E 0276 FSL 1625 FEL

BHL Sec 22 T09S R21E 1079 FSL 1817 FEL

43-047-52613 NBU 921-2201CS Sec 22 T09S R21E 0274 FSL 1635 FEL

BHL Sec 22 T09S R21E 0747 FSL 1816 FEL WELL PAD - NBU 921-22M

43-047-52586 NBU 921-22M1BS Sec 22 T09S R21E 0695 FSL 0660 FWL

BHL Sec 22 T09S R21E 1080 FSL 0823 FWL

43-047-52587 NBU 921-22M1CS Sec 22 T09S R21E 0686 FSL 0654 FWL

BHL Sec 22 T09S R21E 0748 FSL 0823 FWL

43-047-52588 NBU 921-22M4BS Sec 22 T09S R21E 0678 FSL 0649 FWL

BHL Sec 22 T09S R21E 0416 FSL 0823 FWL

43-047-52589 NBU 921-22M4CS Sec 22 T09S R21E 0670 FSL 6043 FWL

BHL Sec 22 T09S R21E 0086 FSL 0823 FWL

Page 3

Page 4

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L Coulthard

Disc. cn=Michael L. Coulthard, o=Bureau of Land Management,
ou=Branch of Minerals, email-Michael_Coulthard@blm.gov, c=US
Date: 2012.05.15 07:17:01 -06'00'

bcc: File - Natural Buttes Unit Division of Oil Gas and Mining Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:5-14-12

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 4/27/2012 API NO. ASSIGNED: 43047525580000

WELL NAME: NBU 921-22C1BS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) PHONE NUMBER: 720 929-6356

CONTACT: Laura Abrams

PROPOSED LOCATION: NENW 22 090S 210E **Permit Tech Review:**

> SURFACE: 0691 FNL 2010 FWL **Engineering Review:**

> **BOTTOM: 0085 FNL 2150 FWL** Geology Review:

COUNTY: UINTAH

LATITUDE: 40.02691 LONGITUDE: -109.54009 UTM SURF EASTINGS: 624571.00 NORTHINGS: 4431765.00

FIELD NAME: NATURAL BUTTES LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU0147566 PROPOSED PRODUCING FORMATION(S): BLACKHAWK

SURFACE OWNER: 2 - Indian **COALBED METHANE: NO**

Drilling Unit

RECEIVED AND/OR REVIEWED: LOCATION AND SITING: ✓ PLAT R649-2-3. Unit: NATURAL BUTTES Bond: FEDERAL - WYB000291

Potash R649-3-2. General

Oil Shale 190-3 R649-3-3. Exception

Board Cause No: Cause 173-14 Water Permit: 43-8496

Effective Date: 12/2/1999 **RDCC Review:**

Siting: Suspends General Siting Fee Surface Agreement

✓ Intent to Commingle R649-3-11. Directional Drill

Commingling Approved


Oil Shale 190-5

Oil Shale 190-13

Comments: Presite Completed

Stipulations:

3 - Commingling - ddoucet 4 - Federal Approval - dmason 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 921-22C1BS API Well Number: 43047525580000 Lease Number: UTU0147566

Surface Owner: INDIAN Approval Date: 6/14/2012

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the BLACKHAWK Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingle:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at http://oilgas.ogm.utah.gov

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
 - Requests to Change Plans (Form 9) due prior to implementation
 - Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
 - Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas Form 3160-3 (August 2007)

REVED

FORM APPROVED OMB No. 1004-0136 Expires July 31, 2010

UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT JAN 1 0 2012

5. Lease Serial No. UTU0147566

APPLICATION FOR PERMIT	to dr ibloky rebyterna! Utal	6. If Indian, Allottee or Tribe	Name
1a. Type of Work: DRILL REENTER		7. If Unit or CA Agreement, I UTU63047A	Name and No.
1b. Type of Well: ☐ Oil Well ☐ Ot	her Single Zone Multiple Zone	8. Lease Name and Well No. NBU 921-22C1BS	
2. Name of Operator Contact: KERR MCGEE OIL&GAS ONSHOREM & PLaura. A	LAURA ABRAMS brams@anadarko.com	9. API Well No.	2558
3a. Address PO BOX 173779 DENVER, CO 80202-3779	3b. Phone No. (include area code) Ph: 720-929-6356 Fx: 720-929-7356	10. Field and Pool, or Explora NATURAL BUTTES	
4. Location of Well (Report location clearly and in accorded	nnce with any State requirements.*)	11. Sec., T., R., M., or Blk. an	id Survey or Area
At surface NENW 691FNL 2010FWL	40.026928 N Lat, 109.540129 W Lon	Sec 22 T9S R21E Me	r SLB
At proposed prod. zone NENW 85FNL 2150FWL 4	0.028588 N Lat, 109.539628 W Lon		
 Distance in miles and direction from nearest town or post APPROXIMATELY 44.4 MILES SOUTH OF VEI 		12. County or Parish UINTAH	13. State UT
 Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 85' 	16. No. of Acres in Lease 160.00	17. Spacing Unit dedicated to	this well
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft.	19. Proposed Depth	20. BLM/BIA Bond No. on fil	le
446'	11259 MD 11195 TVD	WYB000291	
 Elevations (Show whether DF, KB, RT, GL, etc. 4823 GL 	22. Approximate date work will start 06/30/2012	23. Estimated duration 60-90 DAYS	
	24. Attachments		7 2012
The following, completed in accordance with the requirements of	f Onshore Oil and Gas Order No. 1, shall be attached to the	ais form:	GAS & MINING
Well plat certified by a registered surveyor. A Drilling Plan. A Surface Use Plan (if the location is on National Forest System SUPO shall be filed with the appropriate Forest Service Off	em Lands, the Item 20 above). 5. Operator certification	ns unless covered by an existing to	bond on file (see
25. Signature (Electronic Submission)	Name (Printed/Typed) LAURA ABRAMS Ph: 720-929-6356		Date 12/16/2011
Title REGULATORY ANALYST II			
Approved by (Signature)	Name (Printed/Typed)	1	Date
Title Assistant Field Manager Lands & Mineral Resources	VERNAL FIELD OFFICE		
application approval does not warrant or certify the applicant hole perations thereon. conditions of approval, if any, are attached.	ds legal or equitable title to those rights in the subject lea	se which would entitle the applic	ant to conduct
itle 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, m	ake it a crime for any person knowingly and willfully to	make to any department or agenc	y of the United

Additional Operator Remarks (see next page)

UDOGN

Electronic Submission #126050 verified by the BLM Well Information System For KERR MCGEE OIL&GAS ONSHORE, LP, sent to the Vernal

NOTICE OF APPROVAL

CONDITIONS OF APPROVAL ATTACHED

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

MPD Dachod Iliola



UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT VERNAL FIELD OFFICE** 170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company:	Kerr McGee Oil & Gas Onshore LP	Location:	NENW, Sec. 22, T9S R21E
Well No:	NBU 921-22C1BS	Lease No:	UTU-0147566
API No:	43-047-52558	Agreement:	Natural Buttes

OFFICE NUMBER:

(435) 781-4400

OFFICE FAX NUMBER:

(435) 781-3420

A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

NOTIFICATION REQUIREMENTS

Construction Activity (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)	-	The Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist shall be notified at least 48 hours in advance of any construction activity. The Ute Tribal office is open Monday through Thursday.
Construction Completion (Notify Ute Tribe Energy & Minerals Dept. and BLM Environmental Scientist)		Upon completion of the pertinent APD/ROW construction, notify the Ute Tribe Energy & Minerals Dept. for a Tribal Technician to verify the Affidavit of Completion. Notify the BLM Environmental Scientist prior to moving on the drilling rig.
Spud Notice (Notify BLM Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify BLM Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov
BOP & Related Equipment Tests (Notify BLM Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify BLM Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.

Site Specific COA's

- Paint facilities "Shadow Gray"
- Conduct a raptor survey prior to construction operation if such activates would take place during raptor nesting season (January 1- September 30). If active raptor nests are identified during the survey, operations should be conducted according to the seasonal restrictions detailed in the Uinta Basin-specific RMP guidelines and spatial offsets specified by the USFWS Utah
- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct
 a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation
 Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor construction operation with a permitted archaeologist.
- Monitor construction operation with a permitted paleontologist.
- Construct low water crossing on access road.
- Construct diversion pond on west side of well pad to slow runoff.

Pipeline Route from North Compressor to West Cottonwood Compressor

- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct
 a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation
 Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor areas with a permitted paleontologist where pipeline travels through Sections 15, 16,
 17, and 22. Monitor section 27 at the beginning of construction and spot monitor thereafter.

ACTS line

- If construction and/or drilling operations have not been initiated prior to August 8, 2012, conduct
 a biological survey to determine the guidelines specified in the USFWS Rare Plant Conservation
 Measures and the BLM RMP ROD. KMG will implement commitment contained in the GNB BO.
- Monitor areas with a permitted paleontologist where ACTS line travels through Section 15 SWSE, and Section 22 NWNE, NENW, SWSW, and SWSE.

Page 3 of 6 Well: NBU 921-22C1BS 5/29/2012

DOWNHOLE PROGRAM CONDITIONS OF APPROVAL (COAs)

SITE SPECIFIC DOWNHOLE COAs:

- Surface casing cement shall be brought to surface.
- Production casing cement shall be brought 400' up and into the surface casing.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the
 daily drilling report. Components shall be operated and tested as required by Onshore Oil &
 Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be
 performed by a test pump with a chart recorder and <u>NOT</u> by the rig pumps. Test shall be
 reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- Cement baskets shall not be run on surface casing.
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water
 is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM
 Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person

Page 4 of 6 Well: NBU 921-22C1BS 5/29/2012

making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM,
 Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the <u>top of cement</u> and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- Please submit an electronic copy of all other logs run on this well in LAS format to BLM_UT_VN_Welllogs@BLM.gov. This submission will supersede the requirement for submittal of paper logs to the BLM.
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

Page 5 of 6 Well: NBU 921-22C1BS 5/29/2012

OPERATING REQUIREMENT REMINDERS:

 All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.

- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be
 notified when it is placed in a producing status. Such notification will be by written
 communication and must be received in this office by not later than the fifth business day
 following the date on which the well is placed on production. The notification shall provide, as a
 minimum, the following informational items:
 - o Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - o Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if

Page 6 of 6 Well: NBU 921-22C1BS 5/29/2012

performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field
 Office Petroleum Engineers will be provided with a date and time for the initial meter calibration
 and all future meter proving schedules. A copy of the meter calibration reports shall be
 submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API
 standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All
 measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted
 to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs
 first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be
 adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively
 sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office
 Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in
 order that a representative may witness plugging operations. If a well is suspended or
 abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent
 Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual
 plugging of the well bore, showing location of plugs, amount of cement in each, and amount of
 casing left in hole, and the current status of the surface restoration.

SUBMIT AS EMAIL

Print Form

BLM - Vernal Field Office - Notification Form

•	rator KERR-WIGGEE OIL & GAS			
Subr	nitted By <u>L. Urban</u> F	Phone Num	ber <u>720.</u>	<u>929.6501</u>
	Name/Number NBU 921-22C			
	Qtr <u>NE/NW</u> Section 22		<u>s</u> R	lange <u>21E</u>
Leas	e Serial Number <u>UTU0147566</u>	6		
API	Number <u>4304752558</u>			
	d Notice – Spud is the initial below a casing string.	spudding o	of the we	ll, not drilling
	Date/Time <u>11/09/2012</u>	15:00 HRS	AM 🗌	РМ
Casin time ✓	ng – Please report time casing. Surface Casing Intermediate Casing Production Casing Liner Other	ng run stari	ts, not ce	ementing
	Date/Time <u>11/28/2012</u>	08:00 HRS	AM 🔲	PM
BOP	E Initial BOPE test at surface BOPE test at intermediate of 30 day BOPE test Other			RECEIVED NOV 0 8 2012 DIV. OF OIL, GAS & MINING
	Date/Time		AM 🗌	РМ
Rem	arks estimated date and time. Pleas	SE CONTACT KENN	Y GATHINGS	AT
435.82	8.0986 OR LOVEL YOUNG AT 435.781.705	1		

Sundry Number: 32011 API Well Number: 43047525580000

	STATE OF UTAH		FORM 9
ı	DEPARTMENT OF NATURAL RESOURC DIVISION OF OIL, GAS, AND MIN		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU0147566
SUNDR	RY NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In
Do not use this form for pro current bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22C1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047525580000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	h Street, Suite 600, Denver, CO, 80217	PHONE NUMBER: 3779 720 929-0	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL			COUNTY: UINTAH
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NENW Section: 2	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Merio	lian: S	STATE: UTAH
11. CHEC	K APPROPRIATE BOXES TO INDICAT	E NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
SUBSEQUENT REPORT Date of Work Completion:	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
✓ SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud: 11/10/2012	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON
1171072012	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
	WILDCAT WELL DETERMINATION	OTHER	OTHER:
MIRU TRIPLE A BU RAN 14" 36.7# SC	WILDCAT WELL DETERMINATION COMPLETED OPERATIONS. Clearly show a CKET RIG. DRILLED 20" CON HEDULE 10 CONDUCTOR PIF. SPUD WELL LOCATION ON 11:30 HRS.	DUCTOR HOLE TO 40'. PE. CEMENT WITH 28	<u>'</u>
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMB 720 929-6857	ER TITLE Regulatory Analyst II	
SIGNATURE N/A		DATE 11/12/2012	
14/73			

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM

Operator:

KERR McGEE OIL & GAS ONSHORE LP

Operator Account Number: N 2995

WSMVD

Address:

P.O. Box 173779

city DENVER

zip 80217 state CO

Phone Number: _(720) 929-6857

Well 1

API Number	Well	Name	QQ	Sec	Twp	Rng	County
4304752567	NBU 921-22C4C	s	NENW	22	98	21E	UINTAH
Action Code	Current Entity Number	New Entity Number	S	pud Dat	te		ity Assignment iffective Date
В	9999	2900	1	1/10/201	12	11/	15/2012

MIRU TRIPLE A BUCKET RIG.

SPUD WELL LOCATION ON NOVEMBER 10, 2012 AT 08:00 HRS. BHL: New

Well 2

API Number	Well	Name	QQ	Sec	Twp	Rng	County	
4304752558	NBU 921-22C1BS		NENW	22	98	21E	UINTAH	
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date		
B	9999	2900	1	1/10/20	12	11/	15/2012	

Comments:

MIRU TRIPLE A BUCKET RIG.

WSMVD SPUD WELL LOCATION ON NOVEMBER 10, 2012 AT 11:30 HRS. BHL: Nenw

Well 3

API Number Well Nan		Name QQ		Sec	Twp	Rng	County
							UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			y Assignment ective Date	
Comments:				<u>.</u>	<u>.</u>		

ACTION CODES:

- A Establish new entity for new well (single well only)
- **B** Add new well to existing entity (group or unit well)
- C Re-assign well from one existing entity to another existing entity
 D Re-assign well from one existing entity to a new entity
- E Other (Explain in 'comments' section)

NOV 1 3 2012

Lindsey Frazier

Name (Please Print)

Signature

Title

REGULATORY ANALYST II

11/13/2012

Date

بيدانيا أأسيوا تعالم

Sundry Number: 33355 API Well Number: 43047525580000

	STATE OF UTAH				FORM 9
ı	DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MIN		3	5.LEASE UTU01	DESIGNATION AND SERIAL NUMBER: 47566
SUNDR	Y NOTICES AND REPORTS	ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In	
	posals to drill new wells, significantly reenter plugged wells, or to drill horizo n for such proposals.				r CA AGREEMENT NAME: AL BUTTES
1. TYPE OF WELL Gas Well					NAME and NUMBER: 21-22C1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.			9. API NU 43047	JMBER: 525580000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	n Street, Suite 600, Denver, CO, 80217		NE NUMBER: 9 720 929-6		and POOL or WILDCAT: AL BUTTES
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL				COUNTY	
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NENW Section: 2	HP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Meri	dian:	S	STATE: UTAH	
11. CHECK	K APPROPRIATE BOXES TO INDICA	ΓΕ Ν	ATURE OF NOTICE, REPOR	T, OR O	THER DATA
TYPE OF SUBMISSION			TYPE OF ACTION		
	ACIDIZE		ALTER CASING		CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS		CHANGE TUBING		CHANGE WELL NAME
	CHANGE WELL STATUS		COMMINGLE PRODUCING FORMATIONS		CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	□ F	FRACTURE TREAT		NEW CONSTRUCTION
	OPERATOR CHANGE	P	PLUG AND ABANDON		PLUG BACK
SPUD REPORT	PRODUCTION START OR RESUME		RECLAMATION OF WELL SITE		RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION		SIDETRACK TO REPAIR WELL		TEMPORARY ABANDON
	TUBING REPAIR		/ENT OR FLARE	П	WATER DISPOSAL
✓ DRILLING REPORT Report Date:	WATER SHUTOFF		SI TA STATUS EXTENSION	П	APD EXTENSION
1/2/2013			STA STATUS EXTENSION		AFD EXTENSION
	WILDCAT WELL DETERMINATION		OTHER	ОТНЕ	K:
	completed operations. Clearly show the month of December 2012			oi FOI	Accepted by the Utah Division of II, Gas and Mining R RECORD ONLY anuary 03, 2013
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMB 720 929-6857	ER	TITLE Regulatory Analyst II		
SIGNATURE N/A			DATE 1/2/2013		

Sundry Number: 34917 API Well Number: 43047525580000 FEDERAL APPROVAL OF THIS ACTION IS NECESSARY

	STATE OF UTAH		FORM 9					
	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	3	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU0147566					
SUNDF	RY NOTICES AND REPORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In					
Do not use this form for procurrent bottom-hole depth, FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES							
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22C1BS					
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	9. API NUMBER: 43047525580000							
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18t	9. FIELD and POOL or WILDCAT: 5MATURAL BUTTES							
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL	COUNTY: UINTAH							
QTR/QTR, SECTION, TOWNSI Qtr/Qtr: NENW Section:	STATE: UTAH							
11. CHEC	K APPROPRIATE BOXES TO INDICATE N	IATURE OF NOTICE, REPOR	T, OR OTHER DATA					
TYPE OF SUBMISSION		TYPE OF ACTION						
NOTICE OF INTENT Approximate date work will start: 2/21/2013 SUBSEQUENT REPORT Date of Work Completion: SPUD REPORT Date of Spud: DRILLING REPORT Report Date: 12. DESCRIBE PROPOSED OR	ACIDIZE							
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. If extreme mud losses are observed or cement doesn't reach surface on a well on the pad, the operator requests authorization to place a DV tool in the production casing string and run a 2 stage cement job after setting the production casing to ensure cement is properly circulated to surface. Below describes how it will be conducted: Run I-80 casing from TD to approximately 4,950 feet where the DV Tool will be placed. Run a centralizer and cement basket on the I-80 joint below the DV Tool (use a stop ring to keep the CMT Basket at top of the tool joint). Run a DV Tool at approximately 4,950 feet. Run LTC/DXQ crossover. Run a centralizer and a cement basket on the Crossover (use a stop ring to keep the CMT Basket at bottom of the tool joint). Run DXQ casing to surface. The actual depth details will be captured in the well completion report.								
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMBER 720 929-6857	TITLE Regulatory Analyst II						
SIGNATURE N/A		DATE 2/21/2013						


Sundry Number: 34883 API Well Number: 43047525580000 FEDERAL APPROVAL OF THIS ACTION IS NECESSARY

	STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES	3	FORM 9				
ı	DIVISION OF OIL, GAS, AND MININ		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU0147566				
	RY NOTICES AND REPORTS O		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In				
Do not use this form for pro current bottom-hole depth, FOR PERMIT TO DRILL form	oposals to drill new wells, significantly de reenter plugged wells, or to drill horizonta n for such proposals.	epen existing wells below al laterals. Use APPLICATION	7.UNIT OF CA AGREEMENT NAME: NATURAL BUTTES				
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22C1BS				
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	NSHORE, L.P.		9. API NUMBER: 43047525580000				
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl	P h Street, Suite 600, Denver, CO, 80217 3	HONE NUMBER: 779 720 929-6	9. FIELD and POOL or WILDCAT: 5M&TUTRAL BUTTES				
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL	COUNTY: UINTAH						
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Meridia	n: S	STATE: UTAH				
11. CHEC	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	RT, OR OTHER DATA				
TYPE OF SUBMISSION		TYPE OF ACTION					
The operator is refrom a pad, and to the pad based upo periodic well tests NBU 921-22C PAD 4304752570 NE	CHANGE TO PREVIOUS PLANS CHANGE WELL STATUS DEEPEN OPERATOR CHANGE PRODUCTION START OR RESUME REPERFORATE CURRENT FORMATION TUBING REPAIR WATER SHUTOFF WILDCAT WELL DETERMINATION COMPLETED OPERATIONS. Clearly show all questing the option to measure allocate gas production to the on multi-phase flow measurems. Please see the attached doc 3: NBU 921-22F4BS 4304752569 IV 921-22F1BS 4304752569 IV 921-22C1BS 43047	e total gas produced e individual wells on ent at each well and cuments. Thank you. 71 NBU 921-22F1CS NBU 921-22C4CS	CASING REPAIR CHANGE WELL NAME CONVERT WELL TYPE NEW CONSTRUCTION PLUG BACK RECOMPLETE DIFFERENT FORMATION TEMPORARY ABANDON WATER DISPOSAL APD EXTENSION OTHER: Multi-Phase Meter Depths, volumes, etc. Approved by the Utah Division of Oil, Gas and Mining Date: March 07, 2013 By: Depth County Count				
NAME (PLEASE PRINT) Lindsey Frazier	PHONE NUMBER 720 929-6857	TITLE Regulatory Analyst II					
SIGNATURE N/A		DATE 2/21/2013					

Sundry Number: 34883 API Well Number: 43047525580000

The fluids from each well will be measured utilizing a multi-phase flow meter and then directed to a common separator for all wells on the pad. Liquids would be directed to tanks and the gas from all the wells measured through a calibrated orifice meter. The volume of gas measured through this meter, plus fuel gas consumed on location, will be the volume of gas that is produced from the pad. Gas volume for each individual well on the pad will be based on an allocation formula utilizing the total pad volume measured plus fuel gas consumed and the calculated volume from each well utilizing the multi-phase flow meters. The multi-phase flow meter volume calculation will be calibrated by periodic individual well tests.

RECEIVED: Feb. 21, 2013



Sundry Number: 36536 API Well Number: 43047525580000

	STATE OF UTAH				FORM 9			
ı	DEPARTMENT OF NATURAL RESOUR DIVISION OF OIL, GAS, AND MII	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU0147566						
	Y NOTICES AND REPORTS			6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In				
	posals to drill new wells, significantly reenter plugged wells, or to drill horizon for such proposals.			7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES				
1. TYPE OF WELL Gas Well				8. WELL NAME and NUMBER: NBU 921-22C1BS				
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	9. API NUMBER: 43047525580000							
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	9. FIELD and POOL or 5NATURAL BUTTES	WILDCAT:						
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL	COUNTY: UINTAH							
	RTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NENW Section: 22 Township: 09.0S Range: 21.0E Meridian: S							
11. CHECI	K APPROPRIATE BOXES TO INDICA	TE N	ATURE OF NOTICE, REPOR	T, OR OTHER DATA	4			
TYPE OF SUBMISSION			TYPE OF ACTION					
	ACIDIZE		LITER CASING	CASING REPAIR				
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS		CHANGE TUBING	CHANGE WELL N	AME			
Approximate date work will start.	CHANGE WELL STATUS		COMMINGLE PRODUCING FORMATIONS	CONVERT WELL	ТҮРЕ			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	□ F	RACTURE TREAT	☐ NEW CONSTRUC	TION			
·	OPERATOR CHANGE	П	LUG AND ABANDON	PLUG BACK				
SPUD REPORT	PRODUCTION START OR RESUME	□ 6	ECLAMATION OF WELL SITE	RECOMPLETE DI	FERENT FORMATION			
Date of Spud:	REPERFORATE CURRENT FORMATION		SIDETRACK TO REPAIR WELL	TEMPORARY ABA	ANDON			
	TUBING REPAIR		ENT OR FLARE	WATER DISPOSAL				
✓ DRILLING REPORT	WATER SHUTOFF	_	I TA STATUS EXTENSION	APD EXTENSION	-			
Report Date: 4/5/2013								
	WILDCAT WELL DETERMINATION		THER	OTHER:				
	completed operations. Clearly show and ran production casing,			Accepted Utah Divis Oil, Gas and FOR REC April 24,	ion of Mining ORD ONLY			
NAME (PLEASE PRINT)	PHONE NUMB	BER	TITLE					
Doreen Green	435 781-9758		Regulatory Analyst II					
SIGNATURE N/A			DATE 4/5/2013					

Sundry Number: 37534 API Well Number: 43047525580000

	STATE OF UTAH		FORM 9
l I	DEPARTMENT OF NATURAL RESOUR DIVISION OF OIL, GAS, AND MI		5.LEASE DESIGNATION AND SERIAL NUMBER: UTU0147566
SUNDR	Y NOTICES AND REPORTS	ON WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In
	posals to drill new wells, significantly reenter plugged wells, or to drill horiz n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22C1BS
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047525580000
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES		
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL	COUNTY: UINTAH		
QTR/QTR, SECTION, TOWNSH Qtr/Qtr: NENW Section: 2	HIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Mei	ridian: S	STATE: UTAH
11. CHECI	K APPROPRIATE BOXES TO INDICA	ATE NATURE OF NOTICE, REPOR	RT, OR OTHER DATA
TYPE OF SUBMISSION		TYPE OF ACTION	
	ACIDIZE	ALTER CASING	CASING REPAIR
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME
	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	☐ TEMPORARY ABANDON
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL
DRILLING REPORT Report Date:	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION
5/3/2013	WILDCAT WELL DETERMINATION	OTHER	OTHER:
40 DECODINE DRODOGED OF		United by the best of the best	<u> </u>
l .	the month of April 2013. V		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY May 09, 2013
NAME (PLEASE PRINT)	PHONE NUM	BER TITLE	
Luke Urban	720 929-6501	Regulatory Specialist	
SIGNATURE N/A		DATE 5/3/2013	

RECEIVED: May. 03, 2013

Sundry Number: 38408 API Well Number: 43047525580000

	STATE OF UTAH		FORM 9				
ı	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MININ	G	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU0147566				
SUNDR	Y NOTICES AND REPORTS ON	I WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ute In				
Do not use this form for pro current bottom-hole depth, I FOR PERMIT TO DRILL form	7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES						
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 921-22C1BS				
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	9. API NUMBER: 43047525580000						
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	Ph n Street, Suite 600, Denver, CO, 80217 37	IONE NUMBER: 779 720 929-6	9. FIELD and POOL or WILDCAT: 65NIATURAL BUTTES				
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0691 FNL 2010 FWL	COUNTY: UINTAH						
QTR/QTR, SECTION, TOWNSH	IIP, RANGE, MERIDIAN: 22 Township: 09.0S Range: 21.0E Meridian	n: S	STATE: UTAH				
11. CHECK	K APPROPRIATE BOXES TO INDICATE	NATURE OF NOTICE, REPOR	T, OR OTHER DATA				
TYPE OF SUBMISSION		TYPE OF ACTION					
	ACIDIZE	ALTER CASING	CASING REPAIR				
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHANGE TUBING	CHANGE WELL NAME				
Approximate date work will start.	CHANGE WELL STATUS	COMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE				
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRACTURE TREAT	NEW CONSTRUCTION				
	OPERATOR CHANGE	PLUG AND ABANDON	PLUG BACK				
SPUD REPORT	PRODUCTION START OR RESUME	RECLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION				
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDETRACK TO REPAIR WELL	TEMPORARY ABANDON				
	TUBING REPAIR	VENT OR FLARE	WATER DISPOSAL				
✓ DRILLING REPORT	WATER SHUTOFF	SI TA STATUS EXTENSION	APD EXTENSION				
Report Date: 6/3/2013							
	WILDCAT WELL DETERMINATION	OTHER	OTHER:				
	COMPLETED OPERATIONS. Clearly show all perompleting the well. Well TD at	_	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 10, 2013				
NAME (PLEASE PRINT) Matthew P Wold	PHONE NUMBER 720 929-6993	TITLE Regulatory Analyst I					
SIGNATURE N/A		DATE 6/3/2013					

(August 2007)			DEPAR BUREAU	TMEN	T OF		INTERIO								OM	B No. 1	1004-0137 y 31, 2010
	WELL (COMPL	ETION C	R RE	COI	MPLE	TION R	EPO	RT	AND L	.OG				ease Serial N ITU014756		
1a. Type of	f Well	Oil Well	⊠ Gas '	Well		Dry [Other						Ì	6. If	Indian, Allo	ottee o	r Tribe Name
b. Type o	e of Completion New Well Work Over Deepen Plug Back Diff. Resvr. Other										svr.	7. Uı	nit or CA A	greem	ent Name and No.		
2. Name of	Operator	&GAS O	NSHORE	-Mail∙t			t: TEENA		0					8. Lease Name and Well No. NBU 921-22C1BS			
	PO BOX 1	73779	·	-iiviaii. t	oona.	.paulo e	3a	. Phone		. (include	e area co	de)		9. API Well No.			
4. Location	DENVER, n of Well (Rep			ıd in acc	ordan	ice with		n: 720- guireme						10. F	Field and Po	ool, or	43-047-52558 Exploratory
At surfa	ice NENW	691FNL	2010FWL	40.026	928 N	l Lat, 10	09.540129	9 W Lo	'n					N	IATURAL I	BUTT	Block and Survey
At top p	orod interval r	eported be	elow NEN	IW 88F	NL 2	149FW	L							O	r Area Sec	22 T	9S R21E Mer SLB
At total depth NENW 108FNL 2161FWL											County or Pa JINTAH	arish	13. State UT				
14. Date S ₁ 11/10/2																	
18. Total D	Depth:	MD TVD	10190 10141		19.	Plug Ba	ck T.D.:	MD TV			154 105		20. Dep	h Bri	dge Plug Se	t:	MD TVD
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) CBL/GR/CCL/TEMP 22. Was well cored? No Yes (Submit analy Was DST run? No Yes (Submit analy Directional Survey? No Yes (Submit analy Directional Survey)									s (Submit analysis) s (Submit analysis)								
23. Casing a	nd Liner Reco	ord (Repo	rt all strings	set in w	ell)											_	
Hole Size	Size/G		Wt. (#/ft.)	To (MI	D) (MD) Depth Type of Cement (B)				Slurry (BBI	I Cement Lon* I Amou		Amount Pulled					
7.875		25 IJ-55 0 P-110	28.0 11.6		26 2906 730 26 10200 1810						0 515						
7.013	4.50	0 F-110	11.0		20	10	200				10	510				313	
							_										
24. Tubing	Record			l													l .
	Depth Set (M		acker Depth	(MD)	Siz	ze l	Depth Set ((MD)	Pa	acker Dep	oth (MD)	Size	De	pth Set (MI	D)	Packer Depth (MD)
2.375 25. Produci	ng Intervals	9541					26. Perfo	ration R	Reco	rd							
	ormation		Тор		Bot	ttom		Perfora				Π	Size	Т	No. Holes		Perf. Status
A)	WASA	тсн		6910		7768					O 7768		0.36	\neg		OPE	
В)	MESAVE	RDE		8006		9921				8006 T	O 9921		0.36	0	171	OPE	N
C)														\perp			
D)	racture, Treat	mont Con	nant Causage	Eto													
	Depth Interva		nent Squeeze	, Etc.					Δπ	nount and	1 Type o	f Ma	terial				
		10 TO 99	21 PUMP 1	2,028 B	BLS S	SLICK H	2O & 280,0	72 LBS					ittiai				
	ion - Interval		1_	I			T						1.				
Date First Produced 06/05/2013	Test Date 06/08/2013	Hours Tested 24	Test Production	Oil BBL 0.0	N	Gas MCF 1772.0	Water BBL 0.0	C	Oil Gra Corr. A		Ga Gra	s avity		Producti	ion Method FLOV	VS FR	OM WELL
Choke Size 20/64	Tbg. Press. Flwg. 1588 SI	Csg. Press. 2474.0	24 Hr. Rate	Oil BBL 0		Gas MCF 1772	Water BBL		Gas:Oi Ratio	1	We	ell Sta	tus SW				
28a. Produc	ction - Interva	1 B															
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL		Gas MCF	Water BBL		Oil Gra Corr. A		Ga Gra	s avity		Producti	ion Method		

24 Hr.

Rate

Oil

Tbg. Press. Flwg.

Choke

Size

Gas MCF

Water BBL

Gas:Oil

Ratio

Well Status

Oil Ga BBL Mc Oil Ga BBL Mc Oil Ga BBL Mc Oil Ga BBL Mc Oil Ga Contents thereof:	S Water BBL Water BBL S Water BBL Cored intervals arol open, flowing an	Oil Gravity Corr. API Gas:Oil Ratio Oil Gravity Corr. API Gas:Oil Ratio dall drill-stem and shut-in pressures tions, Contents, etc.		Production Method Production Method Production Method Production Method Name REEN RIVER	Top Meas. Depth
Oil BBL Mo Oil BBL Mo Oil Ga BBL Mo oited, etc.) Fers): contents thereof: ion used, time to	S Water CF BBL S Water BBL Cored intervals and open, flowing and	Oil Gravity Corr. API Gas:Oil Ratio ad all drill-stem and shut-in pressures	Gas Gravity Well Status	Formation (Log) Markers Name	Meas. Depth
BBL Mo Oil Ga BBL Mo otted, etc.) Gers): contents thereof: ion used, time to	CF BBL Water CF BBL Cored intervals an ol open, flowing an	Gas:Oil Ratio	Gravity Well Status	Formation (Log) Markers Name	Meas. Depth
BBL Mo Oil Ga BBL Mo otted, etc.) Gers): contents thereof: ion used, time to	CF BBL Water CF BBL Cored intervals an ol open, flowing an	Gas:Oil Ratio	Gravity Well Status	Formation (Log) Markers Name	Meas. Depth
BBL Monted, etc.) Fers): contents thereof: ion used, time to	Cored intervals ar	Ratio nd all drill-stem nd shut-in pressures	31. H	Name	Meas. Depth
Cers): contents thereof: ion used, time to	ol open, flowing an	nd shut-in pressures		Name	Meas. Depth
contents thereof: ion used, time to	ol open, flowing an	nd shut-in pressures		Name	Meas. Depth
ion used, time to	ol open, flowing an	nd shut-in pressures			Meas. Depth
Bottom	Descript	tions, Contents, etc.	9		Meas. Depth
				GREEN RIVER	-
cedure):			N	BIRD'S NEST MAHOGANY WASATCH MESAVERDE	1586 1987 2418 5045 8002
s drilled with a 1 11 inch bit. A l un from surface the chronologic	DV tool was place to 4941 ft; LTC Foal well history, p	ed in the well P-110 csg was run erforation	3. DST I		rectional Survey
	11 inch bit. A lun from surface the chronologic req'd.) at verification ached information tronic Submissi	s drilled with a 12 1/4 inch bit. Ti 11 inch bit. A DV tool was place un from surface to 4941 ft; LTC f the chronological well history, p req'd.) 2. Geolog at verification 6. Core A ached information is complete and c	s drilled with a 12 1/4 inch bit. The remainder 11 inch bit. A DV tool was placed in the well un from surface to 4941 ft; LTC P-110 csg was run the chronological well history, perforation req'd.) 2. Geologic Report to verification 6. Core Analysis ached information is complete and correct as determined tronic Submission #212654 Verified by the BLM We	s drilled with a 12 1/4 inch bit. The remainder 11 inch bit. A DV tool was placed in the well un from surface to 4941 ft; LTC P-110 csg was run the chronological well history, perforation req'd.) 2. Geologic Report 3. DST 1 at verification 6. Core Analysis 7 Other: ached information is complete and correct as determined from all availationic Submission #212654 Verified by the BLM Well Information	s drilled with a 12 1/4 inch bit. The remainder 11 inch bit. A DV tool was placed in the well un from surface to 4941 ft; LTC P-110 csg was run the chronological well history, perforation req'd.) 2. Geologic Report 3. DST Report 4. Dir

Name (please print)	TEENA PAULO	Title STAFF REGULATORY SPECIALIST
Signature	(Electronic Submission)	Date <u>07/05/2013</u>

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fradulent statements or representations as to any matter within its jurisdiction.

						KIES RI				
Operation Summary Report										
Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012										
Project: UTAH-UINTAH Site: NBU					PAD			Rig Name No: PROPETRO 12/12, H&P 298/298		
Event: DRILLING Start Dat				e: 11/8/20	12			End Date: 4/5/2013		
Active Datum: R	KB @4,849.00usft (a	bove Mean S	ea	UWI: NE	E/NW/0/9	/S/21/E/22	2/0/0/26/PM/N/69	91/W/0/2010/0/0		
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation		
12/6/2012	0:00 - 0:30	0.50	DRLSUR	06	Α	Р	(3.3.4)	PICK UP 12.25" BIT & 8" MUD MOTOR		
	0:30 - 1:30	1.00	DRLSUR	02	В	Р		DRILL 12.25"SURFACE HOLE F/44'-210' ROP= 166' @ 166 FPH WOB= 5-15K. RPM= TOP DRIVE~55 / MOTOR ~83 /// TOTAL RPM~138 GPM= 491 @ 120 SPM SPP ON/OFF= 800/500 UP/DN/ROT = 37/33/35 NOV ON LINE MW= 8.5		
	1:30 - 2:00	0.50	DRLSUR	06	Α	Р		TOOH & LAY DOWN 12.25" BIT		
	2:00 - 2:30	0.50	DRLSUR	06	Α	Р		PICK UP 11" BIT, DIR. TOOLS, SCRIBE & TIH		
	2:30 - 6:00	3.50	DRLSUR	02	В	Р		DRILL 11". SURFACE HOLE F/ 210'- 710' ROP= 500' @ 142 FPH WOB= 18-22K. RPM= TOP DRIVE~55 / MOTOR ~83 /// TOTAL RPM~ 138 GPM= 491 @ 120 SPM SPP ON/OFF= 1050/850 UP/DOWN/ ROT= 49/45/47K.~DRAG= 4K TORQUE ON/OFF=2800/1200 NOV ON LINE MW= 8.5 NO HOLE ISSUES		
	6:00 - 12:00	6.00	DRLSUR	02	В	P		DRILL 11". SURFACE HOLE F/ 710'-1390' ROP= 680' @ 113 FPH WOB= 18-22K. RPM= TOP DRIVE~55 / MOTOR ~83 /// TOTAL RPM~ 138 GPM= 491 @ 120 SPM SPP ON/OFF= 1100/900 UP/DOWN/ ROT= 60/50/55K.~DRAG= 5K TORQUE ON/OFF=2800/1200 NOV ON LINE MW= 8.5 SLIDE 72' / 9% 12' ABOVE & 1' LEFT OF TARGET LINE NO HOLE ISSUES		

6/12/2013 3:05:24PM 1

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012 Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 12:00 - 18:00 6.00 DRLSUR 02 Ρ В DRILL 11". SURFACE HOLE F/ 1390'- 2014' ROP= 624' @ 104 FPH WOB= 18-22K. RPM= TOP DRIVE~55 / MOTOR ~83 /// TOTAL RPM~ 138 GPM= 491 @ 120 SPM SPP ON/OFF= 1400/1150 UP/DOWN/ ROT= 70/59/63K.~DRAG= 4k TORQUE ON/OFF=3000/1400 NOV ON LINE MW= 8.5 SLIDE= 30' / 6% 7.5' ABOVE & .5' LEFT OF TARGET LINE NO HOLE ISSUES 18:00 - 0:00 6.00 DRLSUR 02 DRILL 11". SURFACE HOLE F/ 2014'- 2450' ROP= 436'@ 72 FPH WOB= 18-22K. RPM= TOP DRIVE~55 / MOTOR ~83 /// TOTAL RPM~ 138 GPM= 491 @ 120 SPM SPP ON/OFF= 1600/ 1300 UP/DOWN/ ROT= 83/70/75K.~DRAG= 8K TORQUE ON/OFF=3000/1400 NOV ON LINE MW= 8.5 SLIDE 46' / 10% 8' ABOVE & 1' LEFT OF TARGET LINE LOST 50% RETURNS @ 2500' /// AIR ON @ 2200 CFM TO MAINTAIN VOLUME NO OTHER HOLE ISSUES 12/7/2012 0:00 - 5:00 5.00 **DRLSUR** 02 DRILL 11". SURFACE HOLE F/ 2014'- 2450' ROP= 436'@ 72 FPH WOB= 18-22K RPM= TOP DRIVE~55 / MOTOR ~83 /// TOTAL RPM~ 138 GPM= 491 @ 120 SPM SPP ON/OFF= 1650/1450 UP/DOWN/ ROT= 91/79/85K.~DRAG= 6K TORQUE ON/OFF=3000/1400 NOV ON LINE MW= 8.5 SLIDE 55' / 13.5% 8' ABOVE & 3' LEFT OF TARGET LINE LOST 50% RETURNS @ 2500' /// AIR ON @ 2200 CFM TO MAINTAIN VOLUME NO OTHER HOLE ISSUES 5:00 - 7:00 2.00 **DRLSUR** 05 Α CIRCULATE & CONDITION HOLE FOR 8-5/8" SURFACE CSG 7:00 - 10:30 3.50 DRLSUR 06 Р LAY DOWN DRILL STRING & DIR. TOOLS 10:30 - 11:00 0.50 DRLSUR 12 Α Ρ P.ISM FOR RUN CSG /// MOVE PIPE RACKS & CATWALK & MOVE CSG INTO POSITION TO PICK UP 11:00 - 13:00 2.00 **CSGSUR** 12 С Ρ RUN 65 JT'S, 8-5/8", 28#, J-55, LT&C CSG. /// SHOE SET @ 2882' & BAFFLE @ 2838'

6/12/2013 3:05:24PM 2

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012 Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 13:00 - 13:30 0.50 **CSGSUR** 12 Ρ В CIRCULATE CSG /// RUN 200' OF 1" DOWN BACKSIDE, RIG DOWN & MOVE RIG OF WELL /// INSTALL CMT HEAD & PLUG/// PJSM FOR CEMENTING 13:30 - 13:30 0.00 **CSGSUR** 12 Ε RIG UP PUMP TRUCK /// TEST LINES TO 1500 PSI /// PUMP 140 BBLS WATER AHEAD FOLLOWED BY 20 BBL GEL WATER FLUSH /// LEAD = 300sx CLASS G CMT @ 12.0 ppg & 2.86 YIELD /// TAIL= 200sx CLASS G CMT @ 15.8 ppg & 1.15 YIELD /// DROP PLUG & DISPLACE W/ 174 BBL'S WATER /// PLUG DN @ 15:22 12/07/2012 /// BUMP PLUG W/ 950 PSI /// FINAL LIFT = 650 PSI /// CHECK FLOAT- HELD W/ 1BBL BACK /// 50% CIRCULATION THRU OUT JOB & NO CMT TO SURFACE /// PUMP 1ST TOP OUT DOWN 1" W/ 150sx CMT @ 15.8ppg & 1.15 YIELD ~ NO CMT TO SURFACE /// PUMP TOP OUT #2 W/ 80sx CMT ~ CMT TO SURFACE & STAYED RELEASE RIG @ 16:00 12/07/2012 TO NBU 921-22F1CS 14:00 - 15:30 3/29/2013 1.50 MIRU3 01 С 2927 PREPARE & SKID RIG / CENTER OVER WELL 15:30 - 16:30 1.00 MIRU3 01 В Р 2927 RIG UP AFTER SKID 16:30 - 17:00 0.50 **PRPSPD** Р 2927 NIPPLE UP BOP'S & EQUIPMENT 14 Α 17:00 - 22:00 5.00 **PRPSPD** 15 2927 MU TEST ASSY & PRESSURE TEST H&P EQUIPMENT Α - BLIND RAMS PIPE RAMS FLOOR VALVES IBOP& MANUEL VALVE, KILL LINES& KILL VLAVES, BOP WING VALVES.HCR VALVE .INNER & OUTER CHOKE VALVES ,CHOKE MANIFOLD TO 250 PSI LOW FOR 5MINUTES & HIGH TEST TO 5000 PSI FOR 10 MINUTES TEST ANNULAR 250 PSLLOW FOR 5 MINUTES & 2500 PSI FOR 10 MINUTE HIGH TEST / TEST CASING FOR 30 MINUTES @ 1500 PSI 22:00 - 23:00 1.00 **PRPSPD** 15 Α Ρ PRESSURE TEST MI SWACO PRESSURE CONTROL **EQUIPMENT** 23:00 - 23:30 0.50 PRPSPD 14 В Р INSTALL WEAR BUSHING 23:30 - 0:00 0.50 **PRPSPD** Ρ 06 Α PICK & MAKE UP DIRECTIONAL TOOLS WITH WEATHERFORD, SCRIBE, OREINTATE & TEST SAME 3/30/2013 0:00 **PRPSPD** 0 - 1:30 1.50 06 Α Р CONTINUE TO PICK UP BHA & TRIP IN HOLE TO 1:30 - 2:30 1.00 **PRPSPD** 07 В Ρ LEVEL DERRICK & PRE SPUD SAFETY INSPECTION, INSTALL ROTATING HEAD TAG CEMENT @ 2,778' 2:30 - 3:30 1.00 **DRLPRC** F Ρ 2778 02 DRILL OUT CEMENT AND SHOE TRACK FROM 2,778'

6/12/2013 3:05:24PM 3

TO 2,904' - CLEAN OUT RAT HOLE TO 2,927'

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/6/2012 Well: NBU 921-22C1BS ORANGE Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 3:30 - 6:00 2.50 DRLPRC 02 В Ρ 2927 DRILL/SURVEY / SLIDE FROM 2.927' TO 3.375' = 448' = 179.20 FPH WOB 18,000-23,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2,140/1,740 TORQUE ON/OFF BTM 7,000/ 4,000 PICK UP WT 101,000 SLACK OFF WT 91,000 **ROT WT 97,000** SLIDE 38' IN 25 MIN 14.62% OF FOOTAGE DRILLED, 25 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 26 NOV-D WATER SWACO OFF LINE 6:00 - 17:00 11.00 **DRLPRC** 02 В 3375 DRILL/SURVEY / SLIDE FROM 3,375' TO 4,793' = 1,418' = 128.90 FPH WOB 18,000-23,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2,180/1,740 TORQUE ON/OFF BTM 9,000/ 7,000 PICK UP WT 131,000 SLACK OFF WT 111,000 ROT WT 125,000 SLIDE 301' IN 320 MIN 21.23% OF FOOTAGE DRILLED, 48.48 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 26 **NOV-D WATER** SWACO OFF LINE 17:00 - 17:30 0.50 DRLPRC 07 Α Ρ 4793 SERVICE RIG @ 4,793'

				U	S ROC	KIES RE	EGION	
				Opera	tion S	umma	ry Report	
Vell: NBU 921-	22C1BS ORANGE						Spud Date: 12	/6/2012
Project: UTAH-l	UINTAH		Site: NBU	921-220	PAD			Rig Name No: PROPETRO 12/12, H&P 298/298
vent: DRILLIN	IG		Start Date	e: 11/8/20	12			End Date: 4/5/2013
ctive Datum: F	RKB @4,849.00usft (a	bove Mean S	ea	UWI: NE	E/NW/0/9	/S/21/E/22	2/0/0/26/PM/N/69	91/W/0/2010/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
	17:30 - 0:00	6.50	DRLPRC	02	В	P	4793	DRILL/SURVEY / SLIDE FROM 4,793' TO 5,770' = 977' = 150.30 FPH WOB 18,000-23,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2,370/1,970 TORQUE ON/OFF BTM 9,000/ 7,000 PICK UP WT 143,000 SLACK OFF WT 121,000 ROT WT 134,000 SLIDE 53' IN 90 MIN 5.44% OF FOOTAGE DRILLED, 21.43 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 26 NOV-D WATER SWACO OFF LINE
3/31/2013	0:00 - 6:00	6.00	DRLPRV	02	В	P	5770	DRILL/SURVEY / SLIDE FROM 5,770' TO 6,493' =723' = 120.5 FPH WOB 20,000-25,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2,340/2010 TORQUE ON/OFF BTM 10,000/ 7,000 PICK UP WT 166,000 SLACK OFF WT 130,000 ROT WT 146,000 SLIDE 27' IN 45 MIN 4.29% OF FOOTAGE DRILLED, 15 %OF HRS DRILLED PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 26 NOV-D WATER SWACO OFF LINE

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012 Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 6:00 - 16:00 10.00 **DRLPRV** 02 В Ρ 6493 DRILL/SURVEY / SLIDE F/ 6.493' TO 7.249' =756' = 75.6 FPH WOB 20,000-25,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 2,000/1650 TORQUE ON/OFF BTM 9,000/ 8,000 PICK UP WT 176,000 SLACK OFF WT 141,000 **ROT WT 155,000** SLIDE 65' IN 165 MIN 8.60% OF FOOTAGE DRILLED, 27.5%OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 27 **NOV-D WATER** SWACO OFF LINE 16:00 - 16:30 0.50 **DRLPRV** 07 7249 SERVICE RIG @ 7,249' 16:30 - 18:00 Р 1.50 DRLPRV 02 В 7249 DRILL/SURVEY / SLIDE F/ 7,249' TO 7,344' =95' = 63.33 FPH WOB 20,000-25,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 1730/1450 TORQUE ON/OFF BTM 10,000/ 8,000 PICK UP WT 185,000 SLACK OFF WT 145,000 ROT WT 157,000 SLIDE 20' IN 50 MIN 21% OF FOOTAGE DRILLED, 55.5 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 27 NOV-D WATER SWACO OFF LINE 18:00 - 18:30 0.50 **DRLPRV** В Ζ 7344 80 CHANGE OUT ENCODER ON TOP DRIVE *** TOP DRIVE ***

				U	SROC	KIES RE	EGION	
				Opera	tion S	umma	ry Report	
Vell: NBU 921-	22C1BS ORANGE						Spud Date: 12	/6/2012
roject: UTAH-l	UINTAH		Site: NBU	921-220	PAD			Rig Name No: PROPETRO 12/12, H&P 298/298
vent: DRILLIN	IG		Start Date	e: 11/8/20	12			End Date: 4/5/2013
ctive Datum: F evel)	RKB @4,849.00usft (a	bove Mean Se	ea	UWI: NE	E/NW/0/9	/S/21/E/22	2/0/0/26/PM/N/69	91/W/0/2010/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
		5.50	DRLPRV	02			7344	DRILL/SURVEY / SLIDE F/ 7,344' TO 7,715' =371' =67.45' FPH WOB 20,000-25,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 1825/1500 TORQUE ON/OFF BTM 11,000/ 9,000 PICK UP WT 196,000 SLACK OFF WT 145,000 ROT WT 168,000 SLIDE 15' IN 60 MIN 3.98% OF FOOTAGE DRILLED, 16.67 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 27 NOV-D WATER SWACO OFF LINE
4/1/2013	0:00 - 6:00	6.00	DRLPRV	02	В	P	7715	DRILL/SURVEY / SLIDE F/ 7,344' TO 8,100' =385' = 64.16' FPH WOB 22,000-27,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2450/2100 TORQUE ON/OFF BTM 11,000/ 9,000 PICK UP WT 196,000 SLACK OFF WT 145,000 ROT WT 168,000 SLIDE 18' IN 80 MIN 6.34% OF FOOTAGE DRILLED, 26.67 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 27 NOV-D WATER

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012 Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 6:00 - 16:00 10.00 **DRLPRV** 02 В Ρ 8100 DRILL/SURVEY / SLIDE F/ 8.100' TO 8.950' =850' = 85' FPH WOB 22,000-27,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2450/2075 TORQUE ON/OFF BTM 11,000/ 9,000 PICK UP WT 205,000 SLACK OFF WT 161,000 **ROT WT 185,000** SLIDE 33' IN 80 MIN 3.88% OF FOOTAGE DRILLED, 13.33 %OF HRS DRILLED NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 8.5 VIS 27 NOV-D WATER SWACO OFF LINE 5-10' FLARE 16:00 - 16:30 0.50 **DRLPRV** Ρ 8950 SERVICE RIG @ 8,950 16:30 - 0:00 В Р 7.50 DRLPRV 8950 02 DRILL/SURVEY / F/ 8,950' TO 9,465' =515' =68.66' WOB 22,000-27,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 123 PUMPS 130 SPM= 585 GPM PUMP PRESSURE ON/OFF BTM 2450/2075 TORQUE ON/OFF BTM 11,000/ 9,000 PICK UP WT 226,000 SLACK OFF WT 170,000 ROT WT 194,000 NO SLIDES NO FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 9.6 VIS 30 - START MUD UP 100 BBL INCREAMENTS @ 9,400' NOV-D WATER / SHUT DOWN NOV @ 9400' SWACO OFF LINE 5-10' FLARE

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/6/2012 Well: NBU 921-22C1BS ORANGE Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 4/2/2013 0:00 - 7:30 7.50 **DRLPRV** 02 В Ρ 9675 DRILL/SURVEY / F/ 9465' TO 9,718' =253' =33.73' **FPH** WOB 22,000-27,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 2450/2075 TORQUE ON/OFF BTM 11,000/ 9,000 PICK UP WT 226,000 SLACK OFF WT 170,000 **ROT WT 194,000** NO SLIDES 40 BBL FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 11.0 VIS 36 -NOV-D WATER OFF LINE SWACO OFF LINE NO FLARE - SMALL FLOW ON CONNECTIONS 7:30 - 9:00 1.50 **DRLPRV** Ζ 9718 CHANGE OUT VIBRATING HOSE TO MUD PUMPS *** CHANGE OUT VIBRATING HOSE *** 9:00 - 11:30 2.50 DRLPRV 02 В 9718 DRILL/SURVEY / F/ 9,718' TO 9,801' =83' =33.2' FPH WOB 25,000-27,000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 2400/2100 TORQUE ON/OFF BTM 13,000/ 9,000 PICK UP WT 226.000 SLACK OFF WT 175,000 ROT WT 195,000 NO SLIDES 60 BBL FLUID LOST FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 11.1 VIS 36 - LCM 5% NOV-D WATER OFF LINE SWACO OFF LINE NO FLARE 11:30 - 12:00 0.50 **DRLPRV** 07 Ρ 9801 **SERVICE RIG @ 9,801'** Α

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012 Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 12:00 - 14:00 2.00 **DRLPRV** 02 Ρ 9801 DRILL/SURVEY / F/ 9,801' TO 9,887' = 86' = 43' FPH В WOB 25.000-27.000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 2400/2100 TORQUE ON/OFF BTM 13,000/ 9,000 PICK UP WT 226,000 **SLACK OFF WT 175,000** ROT WT 195,000 NO SLIDES 50 BBL FLUID LOST FLUID LOST PUMPING 5-10 BBL SWEEPS EVERY STAND,W/ 3-4% CAL CARB & ANCO FIBER MUD WT 11.2 VIS 36 - LCM 5% NOV-D WATER OFF LINE SWACO OFF LINE NO FLARE 14:00 - 18:00 4.00 DRLPRV 9887 FLOW CHECK - BACK REAM 3 STDS SPOT 90 BBL 12.4 PPG 10% LCM PILL UNABLE TO PULL CONTINUE TO BACK REAM TO 8,500' WELL FLOWING, PUMP & PULL TO 7,900'- 150 BBL MUD LOST 18:00 - 19:00 1.00 **DRLPRV** 05 С 7900 CIRC BTMS UP @ 7,900' / NO MUD CUT SPOT 90 BBL 12.4 PPG 12 % LCM PILL / FLOW CHECK - OK 19:00 - 0:00 06 Р 7900 5.00 DRI PRV Α CONTINUE TO TRIP OUT OF HOLE FROM 7,900' TO BIT LAY DOWN DIRECTIONAL TOOLS & BIT 4/3/2013 0:00 - 8:00 8.00 **DRLPRV** 06 Α Ρ 700 TRIP IN HOLE WITH BIT AND MUD MOTOR #2 TO 9,887' WASH LAST TWO STANDS TO BOTTOM. NO FILL (WASH THROUGH BRIDGES @ 3,645, 4,946', 7,973' AND 8,550' - 100BBL LOSS WHILE WASHING ТО ВОТТОМ 8:00 - 12:30 DRLPRV 9887 4.50 02 В DRILL/SURVEY / F/ 9,887' TO 10,190 T.D.= 303' = 67.3 FPH WOB 25.000-27.000 TOP DRIVE RPM 60-75 MUD MOTOR RPM 104 PUMPS 110 SPM= 495 GPM PUMP PRESSURE ON/OFF BTM 2430/2054 TORQUE ON/OFF BTM 11,000/ 9,000 PICK UP WT 250,000 SLACK OFF WT 156.000 **ROT WT 190.000** NO SLIDES 80 BBL FLUID LOST FLUID LOST MUD WT 11.5 VIS 38 - LCM 5% NOV-D WATER OFF LINE SWACO OFF LINE NO FLARE 12:30 - 13:30 1.00 **DRLPRV** 05 С 10,190 CIRCULATE BOTTOMS UP AND CLEAN HOLE @ 10,190' T.D. 13:30 - 15:00 1.50 DRI PRV 06 F Р 10 190 SHORT TRIP F/10,190' - T/ 9,645' NO PROBLEMS, NO 15:00 - 16:30 1.50 **DRLPRV** 05 С Ρ 10,190 CIRCULATE 2 BOTTOMS UP @ 10,190' 20 BBL LOSS

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Well: NBU 921-22C1BS ORANGE Spud Date: 12/6/2012 Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: PROPETRO 12/12, H&P 298/298 **Event: DRILLING** End Date: 4/5/2013 Start Date: 11/8/2012 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD From Operation Start-End (hr) Code (usft) 16:30 - 0:00 7.50 **DRLPRV** 06 Ρ 10,190 Α TRIP OUT OF HOLE LAYING DOWN TUBULARS FROM 10,190' TO 3,150' 4/4/2013 0:00 - 4:30 4.50 DRLPRV Ρ 3150 06 FINISH TRIP OUT OF HOLE LAYING DOWN Α TUBULARS FROM 3,150' TO BIT # 2 4:30 - 5:00 0.50 DRLPRV Р PULL WEAR BUSHING 14 В 5:00 - 8:00 Р 3.00 **CSGPRO** 12 Α 0 PJSM W/ FRANKS CASING CREW / CHANGE OUT **BALES AND ELEVATORS** 8:00 Р 0 - 18:30 10.50 **CSGPRO** 12 С RUN 4 1/2" PRODUCTION CASING TO 10,174.4' WITH NO PROBLEMS / SHOE @ 10,174.43 / FLOAT COLLAR @ 10,128.99 / MVerde Marker @ 7956.22 / DV TOOL @ 5228.11 / X-O @ 4914.54 18:30 - 20:30 2.00 **CSGPRO** 05 Ρ 10,174 CIRCULATE & CLEAN HOLE CLEAN @ 10.174' .'MEAN WHILE RIG DOWN FRANK'S CASING CREW & HOLD PJSM WITH BJ CEMENTERS 20:30 - 23:00 2.50 **CSGPRO** 12 Ε Р 10,174 RIG UP BJ CEMENTERS / PRESSURE TEST TO 5000 PSI / PUMP 1ST STAGE OF CEMENT / 25 BBLS WATER SPACER / PUMP TAIL CEMENT 1,185 SKS -14.3 PPG - 1.35 YIELD / (285 BBL) / DROP PLUG, DISPLACE,W/ 90 BBLS WATER, 67.4 BBLS 11.5 PPG MUD / PLUG DOWN @ 22:50 HRS LIFT PRESSURE @ 2110 BUMP PRESS @ 2,745 / FLOATS OK / 1.5 BBL MUD BACK TO INVENTORY / GOOD RETURNS THROUGH OUT CEMENT JOB 23:00 - 23:30 0.50 **CSGPRO** 13 Α Ρ 5228 DROP OPENING BOMB, LET GRAVITATE, BJ PRESSURE UP TO 940 PSI OPEN DV TOOL BJ PUMP 10 BBL MUD THEN SWITCH TO RIG PUMP - 0:00 23:30 0.50 **CSGPRO** Ρ 5228 13 Α CIRCULATE WITH RIG PUMP MEANWHILE WAIT ON CEMENT - 25 BBL CEMENT BACK TO SURFACE 4/5/2013 0:00 - 3:00 3.00 **CSGPRO** Ρ 13 Α CIRCULATE WITH RIG PUMPS MEANWHILE WAIT ON CEMENT PJSM W/CEMENTERS 3:00 - 6:00 3.00 **CSGPRO** 12 Ε 2ND STAGE CEMENT PUMP 25 BBLS WATER SPACER, 575 SACKS LEAD @ 12.0 PPG / 2.30 YIELD (235BBLS) TAIL 50 SACKS (10 BBLS)@ 15.8 PPG / 1.16 YIELD DROP PLUG DISPLACE W/ 81 BBLS WATER,PLUG DOWN @ 04:47 HRS,LIFT PRESSURE @ 1169 PSI / BUMP PRESS @ 22643, FLOATS HELD W/ 1 BBL RETURNED TO INVENTORY / DV TOOL CLOSED / 2 BBL CEMENT TO SURFACE / GOOD RETURNS THROUGH OUT JOB / RIG DOWN BJ CEMENTERS

6/12/2013 3:05:24PM 11

Р

Р

R

14

14

6:00 - 7:30

7:30 - 11:00

1.50

3.50

CSGPRO

CSGPRO

FLUSH BOP'S & EQUIPMENT, SET PACK OFF & LAY

NIPPLE DOWN BOP'S & EQUIPMENT / CLEAN PITS

DOWN RUNNING TOOL

RELEASE RIG @ 11:00 4/5/13

General

Customer Information 7:

Representative	Company US ROCKIES REGION
MULESS	Representative Advises

Well/Wellbore Information 1.2

				API
			US ROCKIES REGION	REGION Me
				11
General				Nun
Customer Information				nber:
Company	US ROCKIES REGION			4
Representative				30
Address)4
Well/Wellbore Information	rtion			7525
Well	NBU 921-22C1BS ORANGE	Wellbore No.	Ю	580
Well Name	NBU 921-22C1BS	Wellbore Name	NBU 921-22C1BS	00
Report No.	1	Report Date	5/20/2013	00
Project	UTAH-UINTAH	Site	NBU 921-22CPAD)
Rig Name/No.		Event	COMPLETION	
Start Date	6/4/2013	End Date	6/5/2013	
Spud Date	12/6/2012	Active Datum	RKB @4,849.00usft (above Mean Sea Level)	
UWI	NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0			

General ..

Contractor	Job Method	Supervisor	
Perforated Assembly	Conveyed Method		

Summary

1.5

Initial Conditions 4.1

Fluid Type		Fluid Density	Gross Interval	6,910.0 (usft)-9,921.0 (usft Start Date/Time	5/20/2013 12:00AM
Surface Press		Estimate Res Press	No. of Intervals	63 End Date/Time	5/20/2013 12:00AM
TVD Fluid Top		Fluid Head	Total Shots	228 Net Perforation Interval	74.00 (usft)
Hydrostatic Press		Press Difference	Avg Shot Density	3.08 (shot/ft) Final Surface Pressure	
Balance Cond NEUTRAL	NEUTRAL			Final Press Date	

Intervals

Perforated Interval 2.1

June 12, 2013 at 3:10 pm

Date	Formation/	@Toc	CCL-T	MD Top	MD Base	Shot	Misfires/	Diamete	Carr Type /Stage No	Carr	Phasing	Phasing Charge Desc /Charge	Charge	Reason	Misrun
	Reservoir	(nst)	တ	(nstt)	(usft) S (usft) (usft) Density	Density	Add. Shot	_		Size	©	Manufacturer	Weight		
			(nst)			(shot/ft)		Ē		Ē			(gram)		
5/20/2013 WASATCH/	VASATCH/			6.910.0	6,911.0	4.00		0.360 EXP/	EXP/	3.375	90.00		23.00	23.00 PRODUCTIO	
12:00AM														z	

OpenWells

Perforated Interval (Continued) 2.1

200	Derferested Interval (Continued)		 											US ROCKIES REGION	
Date	Formation/ Reservoir	(JJsn)	CCL-T	MD Top (usft)	MD Base (usft)	Shot Mis Density Add	Misfires/ D	Diamete r	Carr Type /Stage No	Carr	Phasing (*)	Charge Desc /Charge Manufacturer	Charge Weight	Reason	Number Wistru Wistru
5/20/2013 12:00AM	WASATCH/			6,937.0	6,938.0	4.00		98	EXP/	3.375	90.06		23.00	23.00 PRODUCTIO	: 4
5/20/2013 12:00AM	WASATCH/			6,993.0	6,994.0	4.00		0.360 E)	EXP/	3.375	90.00		23.00	23.00 PRODUCTIO N	1304
5/20/2013 12:00AM	WASATCH/			7,014.0	7,015.0	4.00		0.360 EXP/	XP/	3.375	90.00		23.00	23.00 PRODUCTIO N	475:
5/20/2013 12:00AM	WASATCH/			7,024.0	7,026.0	4.00		0.360 E)	EXP/	3.375	90.00		23.00	23.00 PRODUCTIO N	255
5/20/2013 12:00AM	WASATCH/			7,194.0	7,195.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	800
5/20/2013 12:00AM	WASATCH/			7,340.0	7,341.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	00
5/20/2013 12:00AM	WASATCH/			7,357.0	7,358.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	WASATCH/			7,369.0	7,370.0	3.00		0.360 EXP/	XP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	WASATCH/			7,380.0	7,381.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	WASATCH/			7,434.0	7,435.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	WASATCH/			7,444.0	7,445.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	WASATCH/			7,758.0	7,760.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	WASATCH/			7,766.0	7,768.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,006.0	8,008.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,024.0	8,026.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,135.0	8,136.0	3.00		0.360 EXP/	XP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,153.0	8,154.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,268.0	8,269.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,284.0	8,285.0	3.00		0.360 E)	EXP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,310.0	8,311.0	3.00		0.360 EXP/	XP/	3.375	120.00		23.00	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,356.0	8,357.0	3.00		0.360 EXP/	XP/	3.375	120.00		23.00	23.00 PRODUCTIO N	

Perforated Interval (Continued)

												S _D	US ROCKIES REGION	
2.1 Pe	Perforated Interval (Continued)	(Continu	ed)											ell Nu
Date	Formation/ Reservoir	(Jsn)	CCL-T S (usft)	MD Top (usft)	MD Base (usft)	Shot Misfires/ Density Add. Shot (shot/ft)	s/ Diamete not r (in)	e Carr Type /Stage No	Carr Size (in)	Phasing (*)	Charge Desc /Charge Manufacturer	Charge Weight (gram)	Reason	umber
5/20/2013 12:00AM	MESAVERDE/			8,372.0	8,373.0	3.00	0.360	30 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	: 4
5/20/2013 12:00AM	MESAVERDE/			8,460.0	8,461.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(N	23.00 PRODUCTIO N	304
5/20/2013 12:00AM	MESAVERDE/			8,476.0	8,477.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	175
m	MESAVERDE/			8,494.0	8,495.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	255
5/20/2013 12:00AM	MESAVERDE/			8,530.0	8,531.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	800
m	MESAVERDE/			8,596.0	8,597.0	3.00	98:0	0.360 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	00
6	MESAVERDE/			8,614.0	8,615.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,650.0	8,651.0	3.00	0.36	0.360 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,768.0	8,770.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,856.0	8,858.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,958.0	8,960.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			8,972.0	8,974.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(N	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			9,144.0	9,145.0	3.00	0.360	30 EXP/	3.375	120.00		23.00 PR(N	23.00 PRODUCTIO	
5/20/2013 12:00AM	MESAVERDE/			9,161.0	9,162.0	3.00	0.360	30 EXP/	3.375	120.00		23.00 PR(N	23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			9,172.0	9,173.0	3.00	0.360	30 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO	
5/20/2013 12:00AM	MESAVERDE/			9,188.0	9,189.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(N	23.00 PRODUCTIO N	
m	MESAVERDE/			9,265.0	9,266.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			9,276.0	9,277.0	3.00	0.360	50 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			9,315.0	9,316.0	3.00	0.360	30 EXP/	3.375	120.00		23.00 PR(N	23.00 PRODUCTIO N	
				9,326.0	9,327.0	3.00	98:0	0.360 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	
5/20/2013 12:00AM	MESAVERDE/			9,364.0	9,365.0	3.00	0.36	0.360 EXP/	3.375	120.00		23.00 PR(23.00 PRODUCTIO N	

June 12, 2013 at 3:10 pm

Perforated Interval (Continued) 2.1

API We	LL Nu 	mber 5	: 4	304	475	255	800	00														
S REG		Misrun																				
US ROCKIES REGION		Reason	23.00 PRODUCTIO N	23.00 PRODUCTIO	23.00 PRODUCTIO N	23.00 PRODUCTIO N	23.00 PRODUCTIO	23.00 PRODUCTIO	23.00 PRODUCTIO N	23.00 PRODUCTIO N	23.00 PRODUCTIO N	23.00 PRODUCTIO	23.00 PRODUCTIO	23.00 PRODUCTIO N	23.00 PRODUCTIO N	23.00 PRODUCTIO N	23.00 PRODUCTIO					
		Charge Weight (gram)	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00	23.00
		Phasing Charge Desc /Charge (*) Manufacturer	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00	120.00
		Carr Size (in)	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375	3.375
		Carr Type /Stage No	0 EXP/	5 EXP/	0.360 EXP/	D EXP/	0 EXP/) EXP/) EXP/) EXP/	0.360 EXP/	D EXP/	0.360 EXP/	0 EXP/	0 EXP/	0 EXP/	5 EXP/	EXP/	0 EXP/	0 EXP/	0.360 EXP/	0.360 EXP/
		Diamete r (in)	0.360	0.360	0.360	0.360	0.360	0.360	0.360	0.360	0.36(0.360	0.36(0.360	0.360	0.360	0.360	0.360	0.360	0.360	0.36(0.36(
		Misfires/ Add. Shot																				
		Shot Density (shot/ft)	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00	3.00
		MD Base (usft)	9,377.0	9,395.0	9,431.0	9,463.0	9,479.0	9,495.0	9,562.0	9,593.0	9,605.0	9,621.0	9,635.0	9,668.0	9,731.0	9,785.0	9,793.0	9,804.0	9,855.0	9,898.0	0.909.0	9,921.0
		T MD Top (usft)	9,376.0	9,394.0	9,430.0	9,462.0	9,478.0	9,494.0	9,560.0	9,592.0	9,604.0	9,620.0	9,634.0	9,666.0	9,730.0	9,784.0	9,792.0	9,803.0	9,854.0	9,897.0	9,908.0	9,920.0
	ed)	S (msft)																				
	(Confinu	(JJSN)																				
	Perforated Interval (Continued)	Formation/ Reservoir	MESAVERDE/	MESAVERDE/																		
	2.1 Pe	Date	5/20/2013 12:00AM	5/20/2013																		

Plots

June 12, 2013 at 3:10 pm

OpenWells

RECEIVED: Jul. 05, 2013

					S ROCI		EGION ary Report	
				Opera		umme	•	2004
-	22C1BS ORANGE		Site: NBL	1 024 226	, DVD		Spud Date: 12/6	
Project: UTAH-L						1		Rig Name No:
Event: COMPLE	-		Start Date	1		10/04/15/0	0.10.10.10.0.0.10.0.0.10.0.0.10.0.0.10.0.0.10.0.0.10	End Date: 6/5/2013
Active Datum: F Level)	RKB @4,849.00usft (a	above Mean S	ea	UWI: NE	=/NVV/0/9/	S/21/E/2	2/0/0/26/PM/N/69	1/W/0/2010/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation
4/26/2013	7:00 - 7:15	0.25	SUBSPR	48		Р		HSM, JSA
	7:15 - 9:00	1.75	SUBSPR	30	Α	Р		MIRU, ND WH, NU BOP'S, RU FLOOR & TBG EQUIP, SPOT IN TBG TRAILER
	9:00 - 11:30	2.50	SUBSPR	31	I	Р		P/U 3-7/8" ROCK BIT, TIH W/ 2-3/8" TBG, TAG TOC @ 5,180'
	11:30 - 13:00	1.50	SUBSPR	44	В	Р		MIRU PWR SWVL, D/O 48' OF CEMENT & DV TOOL, CIRC WELL CLEAN
	13:00 - 15:00	2.00	SUBSPR	31	1	Р		TIH W/ 2-3/8" TBG, TAG FILL @ 10,122'
	15:00 - 17:00	2.00	SUBSPR	44	D	Р		C/O 15' OF FILL TO 10,137' & CIRC WELL CLEAN, TOOH LD 10 JTS ON TRAILER, SDFWE
4/29/2013	7:00 - 7:15	0.25	SUBSPR	48		Р		HSM, JSA
	7:15 - 11:30	4.25	SUBSPR	31	1	Р		TOOH & LD 2-3/8" TBG ON TRAILER
	11:30 - 12:30	1.00	SUBSPR	52	F	Р		PRESSURE TEST CSG TO 3000 PSI, OK
4/30/2013	12:30 - 15:00 -	2.50	SUBSPR	30	С	Р		ND BOP'S, NU WH, RDMO
5/6/2013	9:00 - 14:00	5.00	SUBSPR	33	С	Р		REMOVED TREE SET FRAC VALVES, SURFACE HAD 380 PSI BLED WELL DOWN FILLED SURFACE & CSG TO TEST IN AM
5/7/2013	5:45 - 6:00	0.25	SUBSPR	33	С	Р		MIRU CAMERON QUICK TEST. PRESSURE TEST CSG & FRAC VALVES 1ST PSI TEST T/ 7000 PSI. HELD FOR 15 MIN LOST 62 PSI. NO COMMUNICATION BUT SLIGHT MIGRATION WITH SURFACE CSG BLEED OFF PSI.
								PRESSURE TEST 8 5/8 X 4 1/2 TO 508 PSI HELD FOR 5 MIN LOST -88 PSI,BLED PSI OFF, REINSTALLED POP OFF SWIFN
5/20/2013	8:00 - 18:00	10.00	FRAC	36	В	Р		NOTE SURFACE CSG HAD 380 STABILIZED PSI PERF STG 1 AS PER DESIGN. FRAC STG 1)WHP 432 PSI, BRK 3677 PSI @ 4.9 BPM. ISIP 2908 PSI, FG. 0.73 ISIP 3043 PSI, FG. 0.75,
								NPI 135 PSI. SWI, XO T/ WL.
5/21/2013	6:45 - 7:00	0.25	FRAC	48		Р		HSM. HIGH PSI LINES.

6/12/2013 3:11:31PM 1

				U	SROC	KIES RI	-GION	
				Opera	tion S	umma	ry Report	
Well: NBU 921	-22C1BS ORANGE						Spud Date: 12	/6/2012
Project: UTAH-	UINTAH		Site: NBI	J 921-220	PAD		<u> </u>	Rig Name No:
vent: COMPL	ETION		Start Dat	te: 6/4/201	13			End Date: 6/5/2013
ctive Datum:	RKB @4,849.00usft (a	above Mean S	- 1			/S/21/E/2	2/0/0/26/PM/N/69	91/W/0/2010/0/0
evel)								
Date	Time	Duration	Phase	Code	Sub	P/U	MD From	Operation
	7:00 - 18:00	(hr) 11.00	FRAC	36	Code B	P	(usft)	FRAC STG 2)WHP 2621 PSI, BRK 3794 PSI @ 5
	10.00	11.00	TRAC	30	В	Г		BPM. ISIP 2549 PSI, FG. 0.7 ISIP 3207 PSI, FG. 0.77, NPI 658 PSI. SWI, XO T/ WL.
								SET CBP & PERF AS PER STG 3 DESIGN.
								FRAC STG 3)WHP 1424 PSI, BRK 3688 PSI @ 4.8 BPM. ISIP 2783 PSI, FG. 0.73 ISIP 3020 PSI, FG. 0.76, NPI 237 PSI. SWI, XO T/ WL.
								SET CBP & PERF AS PER STG 4 DESIGN.
								FRAC STG 4)WHP 1910 PSI, BRK 3239 PSI @ 4.8 BPM. ISIP 2665 PSI, FG. 0.73 ISIP 2887 PSI, FG. 0.75, NPI 222 PSI. SWI, XO T/ WL.
								SET CBP & PERF STG 5 AS PER DEISIGN.
								FRAC STG 5)WHP 248 PSI, BRK 4773 PSI @ 4.9 BPM. ISIP 2516 PSI, FG. 0.72 ISIP 3035 PSI, FG. 0.78, NPI 519 PSI. SWI, XO T/ WL.
								SET CBP & PERF STG 6 AS PER DESIGN.
								FRAC STG 6)WHP 1413 PSI, BRK 2884 PSI @ 4.9 BPM. ISIP 1507 PSI, FG. 0.61 ISIP 2739 PSI, FG. 0.76, NPI 1232 PSI. SWI, XO T/ WL.
								SET CBP & PERF STG 7 AS PER DESIGN. SWIFN.
5/22/2013	8:30 - 18:00	9.50	FRAC	36	В	Р		FRAC STG 7)WHP 460 PSI, BRK 2777 PSI @ 5.1 BPM. ISIP 2013 PSI, FG. 0.68 ISIP 2566 PSI, FG. 0.75, NPI 553 PSI. SWI, XO T/ WL.
								SET CBP & PERF STG 8 AS PER DESIGN.
								FRAC STG 8)WHP 558 PSI, BRK 2721 PSI @ 5.1 BPM. ISIP 2151 PSI, FG. 0.71 ISIP 2753 PSI, FG. 0.77, NPI 602 PSI. SWI. XO T/ WL.
								SET CBP & PERF STG 9 AS PER DESIGN.
								FRAC STG 9)WHP 742 PSI, BRK 1877 PSI @ 5.1 BPM. ISIP 1552 PSI, FG. 0.65 ISIP 2354 PSI, FG. 0.76, NPI 802 PSI. SWI, XO T/ WL.
								SET CBP & PERF STG 10 AS PER DESIGN.
								FRAC STG 10)WHP 1469 PSI, BRK 2243 PSI @ 5.1 BPM. ISIP 1802 PSI, FG. 0.7 ISIP 1984 PSI, FG. 0.72, NPI 182 PSI. SWI, XO T/ WL.
								PU 4 1/2 8K HAL CBP. RIH SET KILL PLUG @ 6860'. POOH, SWI. READY FOR DRL OUT.
								TOTAL SAND = 280,072 LBS TOTAL CLFL = 12,028 BBLS

6/12/2013 3:11:31PM 2

RECEIVED: Jul. 05, 2013

API Well Number: 43047525580000 US ROCKIES REGION **Operation Summary Report** Spud Date: 12/6/2012 Well: NBU 921-22C1BS ORANGE Project: UTAH-UINTAH Site: NBU 921-22C PAD Rig Name No: Event: COMPLETION Start Date: 6/4/2013 End Date: 6/5/2013 UWI: NE/NW/0/9/S/21/E/22/0/0/26/PM/N/691/W/0/2010/0/0 Active Datum: RKB @4,849.00usft (above Mean Sea Date P/U Phase Code Operation Time Duration Sub MD From Start-End Code (usft) (hr) 7:00 - 7:15 6/4/2013 0.25 **DRLOUT** 48 Ρ JSA= PU TUBING 7:15 - 7:15 0.00 DRLOUT Р 30 MIRU RIG & EQUIP, ND W/H NU BOPS RU FLOOR & TUBING EQUIP PU POBS TALLY & PU TUBING TAG 1ST CBP @ 6860'RU DRILLING EQUIP EST CIRC TEST BOPS TO 3000 PSI DRILL THRU 1ST CBP PLUG #1] DRILL THRU HALLI 8K CBP @ 6860' IN 9 MIN W/ 300 PSI INCREASE PLUG #2] CONTINUE TO RIH TAG SAND @ 7026' (30' FILL) C/O & DRILL THRU HALLI 8K CBP IN 7 MIN W/ 300 PSI INCREASE PLUG #3] CONTINUE TO RIH TAG SAND @ 7440' (35' FILL) C/O & DRILL THRU HALLI 8K CBP IN 9 MIN W/ 400 INCREASE W/ 75 PSI ON CSG ALLOW WELL TO FLOW 45 MIN SIW SDFN 6/5/2013 7:00 - 7:15 0.25 DRLOUT JSA= DRILL PLUGS 48

6/12/2013 3:11:31PM 3


				U	S ROC	VIES KI	GION	
				Opera	tion S	umma	ry Report	
Well: NBU 921-	22C1BS ORANGE						Spud Date: 12/	(6/2012
Project: UTAH-I			Site: NBL	921-220	PAD			Rig Name No:
Event: COMPL	ETION		Start Date	e: 6/4/201	3			End Date: 6/5/2013
Active Datum: F	RKB @4,849.00usft (ab	ove Mean S		1		/S/21/E/22	2/0/0/26/PM/N/69	01/W/0/2010/0/0
₋evel)								
Date	Time	Duration	Phase	Code	Sub	P/U	MD From	Operation
	7:15 - 17:00	(hr) 9.75	DRLOUT	30	Code	P	(usft)	SIWP= 750 PSI OPEN WELL TO PIT CONTINUE TO RIH
	11.00	0.70	BILLOGI	00		·		TO FILL ON PLG #4
								PLUG #4] TAG SAND @ 8021' (35' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8056' IN 9 MIN W/ 400 # INCREASE 150# ON CSG
								PLUG #5] CONTINUE TO RIH TAG SAND @ 8358' (35' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8393' IN 8 MIN W/ 600 # INCREASE 200 PSI ON CSG
								PLUG # 6] CONTINUE TO RIH TAG SAND @ 8646' (35' FILL) C/O & DRILL THRU HALLI 8K CBP @ 8681' IN 8 MIN W/ 500# INCREASE 300# ON CSG
								PLUG #7] CONTINUE TO RIH TAG SAND @8974' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 9004' IN 6 MIN W/ 500# INCREASE 400 ON CSG
								PLUG #8] CONTINUE TO RIH TAG SAND @ 9317' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @ 9347' IN 11 MIN W/ 700# INCREASE 550 ON CSG
								PLUG #9] CONTINUE TO RIH TAG SAND @ 9495' (30' FILL) C/O & DRILL THRU HALLI 8K CBP @9525' IN 7 MIN W/ 500# INCREASE 700# ON CSG
								PLUG #10] CONTINUE TO RIH TAG SAND @ 9683' (15' FILL) C/O & DRILL THRU HALLI 10K CBP @ 9698' IN 12 MIN W/ 700# INCREASE 550 ON CSG
								PBTD] CONTINUE TO RIH TO 10775' DIDNT TAG FILL POOH LD 17 JNTS LAND TUBING ON HNGR EOT @ 9541.12' RD DRILLING EQUIP RD FLOOR & TUBING EQUIP ND BOPS NU W/H DROP BALL PMP OFF BIT @ 2500 PSI SIW NU & TEST FLOW LINE & TO 3000 PSI TURN WELL OVER TO FBC RD RIG MOVE TO NBU 22C4CS RU RIG
								TUBING DETAIL K.B26.0'
								HNGR83" 150 JNTS 2-3/8" J-554734.00' 2-3/8" L-80
								PUP6.03' 155 JNTS 2-3/8"
								L-804772.06' POBS2.20
								, EOT@9541.12'
								TOTAL FLUID PMPED= 12028 BBLS RIG REC= 3800 BBLS
								LEFT TO REC= 8228 BBLS


6/12/2013 3:11:31PM 4

API We	ll Number	4304	752558			KIES RI	EGION	
				Opera	tion S	umma	ary Report	
Well: NBU 921-2	2C1BS ORANGE						Spud Date: 12/6	6/2012
Project: UTAH-UI	NTAH		Site: NBL	J 921-22C	PAD			Rig Name No:
Event: COMPLE	TION		Start Date	e: 6/4/201	3			End Date: 6/5/2013
Active Datum: Rh Level)	KB @4,849.00usft (al	oove Mean Se	ea	UWI: NE	E/NW/0/9	/S/21/E/2	2/0/0/26/PM/N/691	I/W/0/2010/0/0
Date	Time	Duration	Phase	Code	Sub	P/U	MD From	Operation
	Start-End	(hr)			Code		(usft)	
								CTAP DEL 150 JNTS J-55
								& 182 JNTS L-80
								USED 155 JNTS L-80
								RETURNED= 27 JNTS L-80

6/12/2013 3:11:31PM 5

RECEIVED: Jul. 05, 2013





E.Offset (US ft)(Scale:300USft/in)

5D Survey Report

Andarko Petroleum

Natural Buttes Field Name: Site Name:

Well Name: Survey:

NBU 921-22C Pad NBU 921-22C1BS Definitive Survey Weatherford

5D 7.5.3: 15 April 2013, 15:24:15 UTC

Weatherford International Limited

 \sim

Weatherford

5D Survey Report



Surveys for the NBU 921-22C1BS

Convergence Angle: 0.94	atitude: 40.026905	-ongitude : -109.539562			
North Reference : True Cor	Northing: 14539193.12 USft Lat	Easting: 2049271.64 US ft Lo n	GL + 26' RKB		
Units: US ft	:	Position	Site TVD Reference: 4823' GL	Elevation above:4823.00 US ft	Comment:
		Site Name	100 to 1191	NDO 321-220 rau	

	026963	109.539441								Az : 13.06°
Position (Offsets relative to Site Centre)	ft Latitude: 40.026963	Longitude : -109.539441				UWI:	Comment :	Closure Azimuth: 14.5488°		+E / -W: 0.00 US ft
Position	Northing:14539214.80 USft	Easting:2049305.17 US ft	Ground Elevation	3.00 US ft			: 26.00 US ft JS ft	274 US ft	Vertical Section (Position of Origin Relative to Slot)	+N / -S: 0.00 US ft
	+N / -S: 21.12 US ft	+E / -W: 33.88 US ft	Slot TVD Reference: Ground Elevation	Elevation above: 4823.00 US ft	Comment:	Type: Main well	Rig Height <i>Drill Floor</i> : 26.00 US ft Relative to: 4849.00 US ft	Closure Distance: 602.274 US ft	Vertical Section (Posi	
		Slot Name	OBFOCK FCO HAM	NDO 921-220103			o me N		NBU 921-22C1BS	

	Company:		Dip: 0.00°
			Declination: 0.00°
	Comment:		Field Strength: 50000.0 nT
urvey	Survey Tool :		Date: 13/Feb/2013
Survey Name :Definitive Su	Date: 13/Feb/2013	Magnetic Model	Model Name: Default

Weatherford International Limited

5D Survey Report

Survey Tool Ranges	nges										
	Name		Stari	art MD (usft)		End MD	End MD (us ft)		Source Survey	Survey	
	MWC			0.00		287.	2872.00		SDI MWD	1WC	
	MWC			2872.00		1015	10190.00		WFT MWD	٩WD	
Well path created using minimum curvature	ing minimum cu	ırvature								ı	
Survev Points (Relative to	live to centre	centre. TVD relative to Drill Floor	Drill Floor								
ME (US ft)		AZ (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (°)	Longitude (°)	DLS (°/100 US ft)	CL (US ft)	VS (US ft)	Comment
0.00	00.0	0.00	0.00	0.00	00.0	40.026963	-109.539441	0.00	0.00	0.00	
22.00	0.00	0.00	22.00	0.00	0.00	40.026963	-109.539441	00.00	22.00	0.00	
26.00	0.00	0.00	26.00	0.00	00.0	40.026963	-109.539441	00.00	4.00	0.00	
196.00	0.26	198.74	196.00	-0.37	-0.12	40.026962	-109.539441	0.15	170.00	-0.38	
280.00	0.62	191.18	280.00	-0.99	-0.27	40.026960	-109.539442	0.43	84.00	-1.03	
367.00	0.18	332.42	367.00	-1.33	-0.43	40.026959	-109.539443	0.88	87.00	-1.39	
457.00	60.0	343.58	457.00	-1.14	-0.51	40.026960	-109.539443	0.10	00.06	-1.23	
547.00	0.12	340.96	546.99	96.0-	-0.56	40.026960	-109.539443	0.03	90.00	-1.08	
637.00	0.18	8.81	636.99	-0.75	-0.57	40.026961	-109.539443	0.10	00.06	-0.86	
727.00	0.18	199.44	726.99	-0.75	-0.60	40.026961	-109.539443	0.40	90.00	-0.86	
817.00	0.26	190.48	816.99	-1.08	-0.68	40.026960	-109.539443	0.10	90.00	-1.21	
907.00	0.53	352.63	66.906	-0.87	-0.77	40.026961	-109.539444	0.87	90.00	-1.02	
997.00	2.25	7.38	96.96	1.30	-0.60	40.026967	-109.539443	1.94	90.00	1.13	
1087.00	4.48	4.06	1086.80	6.55	-0.12	40.026981	-109.539441	2.49	00.06	92.9	
1177.00	6.52	2.20	1176.38	15.17	0.32	40.027005	-109.539440	2.28	00.06	14.85	
1267.00	7.47	1.51	1265.71	26.12	0.67	40.027035	-109.539439	1.06	00.06	25.60	
1357.00	7.91	0.63	1354.90	38.16	0.89	40.027068	-109.539438	0.51	00.06	37.38	
1447.00	8.53	358.52	1443.98	51.03	0.79	40.027103	-109.539438	0.77	90.00	49.89	
1537.00	8.71	359.23	1532.96	64.51	0.53	40.027140	-109.539439	0.23	00.06	62.96	
1627.00	8.62	359.31	1621.93	78.07	0.35	40.027177	-109.539440	0.10	00.06	76.13	
1717.00	9.04	356.82	1710.87	91.88	-0.12	40.027215	-109.539441	0.63	00.06	89.47	
1807.00	9.15	354.13	1799.74	106.05	-1.24	40.027254	-109.539445	0.49	90.00	103.03	
1897.00	9.15	359.14	1888.59	120.33	-2.08	40.027293	-109.539448	0.88	00.06	116.75	
1987.00	9.06	1.07	1977.46	134.57	-2.06	40.027332	-109.539448	0.35	90.00	130.62	
2077.00	66.6	0.74	2066.22	149.46	-1.83	40.027373	-109.539448	1.04	90.00	145.18	
2167.00	10.20	2.21	2154.82	165.23	-1.42	40.027417	-109.539446	0.37	90.00	160.63	
2257.00	9.50	0.54	2243.50	180.62	-1.04	40.027459	-109.539445	0.84	90.00	175.71	
2347.00	9.50	357.03	2332.26	195.46	-1.36	40.027500	-109.539446	0.64	90.00	190.10	
2437.00	9.67	357.12	2421.01	210.43	-2.12	40.027541	-109.539449	0.19	00.06	204.51	
2527.00	8.97	0.02	2509.82	224.99	-2.50	40.027581	-109.539450	0.94	90.00	218.61	
2617.00	10.38	2.30	2598.54	240.11	-2.17	40.027622	-109.539449	1.62	90.00	233.41	
2707.00	9.76	359.93	2687.15	255.84	-1.85	40.027665	-109.539448	0.83	90.00	248.81	
2797.00	9.67	359.14	2775.86	271.03	-1.98	40.027707	-109.539448	0.18	90.00	263.57	

RECEIVED: Jul. 05, 2013

Weatherford International Limited

5D 7.5.3: 15 April 2013, 15:24:15 UTC

5D Survey Report

3
1
í
7
J
3
-
)
-
3
3
3
á
-
4
3
a
-
)
-
-
3
'n

5D 7.5.3 : 15 April 2013, 15:24:15 UTC

MC (US ft)	Inc (°)	A7 (°)	TVD (US ft)	N.Offset (US ft)	F.Offset (US ft)	Latitude (°)	Longitude (°)	DLS (*/100 US ft)	CL (US ft.)	VS (US ft)	Comment
2872.00	8.71	357.03	2849.90	283.00	-2.36	40.027740	-109.539449	1.36	75.00	275.14	LAST SDI MWD SURVEY
2948.00	89.6	353.83	2924.92	295.10	-3.35	40.027773	-109,539453	1.44	76.00	286.71	FIRST WFT MWD SURVEY
3042.00	9.96	349.36	3017.54	310.95	-5.70	40.027817	-109.539461	0.86	94.00	301.61	
3137.00	96.6	353.33	3111.11	327.18	-8.17	40.027861	-109.539470	0.72	95.00	316.87	
3231.00	9.25	357.29	3203.80	342.80	-9.47	40.027904	-109.539475	1.03	94.00	331.79	
3326.00	9.31	5.29	3297.56	358.08	-9.13	40.027946	-109.539474	1.36	95.00	346.76	
3420.00	9.63	16.66	3390.28	373.18	-6.17	40.027988	-109.539463	2.02	94.00	362.14	
3515.00	10.13	23.41	3483.88	388.46	-0.57	40.028030	-109.539443	1.33	95.00	378.29	
3609.00	9.81	26.79	3576.46	403.20	6.32	40.028070	-109.539418	0.71	94.00	394.20	
3704.00	8.63	23.79	3670.23	416.95	12.84	40.028108	-109,539395	1.34	95.00	409.06	
3798.00	8.75	26.79	3763.15	429.78	18.91	40.028143	-109.539373	0.50	94.00	422.94	
3893.00	8.81	23.91	3857.04	442.88	25.12	40.028179	-109.539351	0.47	95.00	437.10	
3987.00	7.75	27.04	3950.06	455.11	30.92	40.028213	-109.539331	1.22	94.00	450.32	
4081.00	7.69	19.79	4043.21	466.67	35.93	40.028244	-109.539313	1.04	94.00	462.72	
4176.00	7.33	23.50	4137.39	478.21	40.50	40.028276	-109,539296	0.64	95.00	474.99	
4270.00	6.94	23.41	4230.67	488.92	45.14	40.028305	-109,539280	0.42	94.00	486.48	
4365.00	8.06	25.91	4324.85	500.18	50.33	40.028336	-109.539261	1.23	95.00	498.62	
4459.00	8.14	26.26	4417.91	512.07	56.16	40.028369	-109.539240	0.10	94.00	511.52	
4554.00	7.44	21.43	4512.04	523.83	51.38	40.028401	-109.539222	1.01	95.00	524.15	
4648.00	7.28	23.00	4605.26	534.98	65.93	40.028432	-109.539206	0.27	94.00	536.04	
4743.00	7.54	29.11	4699.47	545.97	71.32	40.028462	-109.539186	0.87	95.00	547.96	
4837.00	7.99	34.14	4792.61	556.76	77.98	40.028492	-109.539162	0.87	94.00	559.98	
4931.00	7.13	33.04	4885.79	567.06	84.83	40.028520	-109.539138	0.93	94.00	571.56	
5026.00	5.83	38.86	4980.18	575.76	91.07	40.028544	-109.539116	1.53	95.00	581.45	
5120.00	6.04	44.56	5073.68	583.00	97.54	40.028564	-109.539093	0.67	94.00	589.96	
5215.00	5.46	42.68	5168.20	589.88	104.11	40.028583	-109.539069	0.64	95.00	598.15	
5309.00	4.57	44.65	5261.84	595.84	109.77	40.028599	-109.539049	96.0	94.00	605.23	
5404.00	4.07	46.47	5356.57	600.85	114.88	40.028613	-109.539031	0.55	95.00	611.27	
5498.00	3.62	51.90	5450.36	604.98	119.63	40.028624	-109.539014	0.62	94.00	616.36	
5592.00	3.08	58.69	5544.20	608.12	124.12	40.028633	-109.538998	0.71	94.00	620.44	
5687.00	2.80	65.50	5639.07	610.41	128.41	40.028639	-109.538982	0.47	95.00	623.64	
5781.00	2.56	71.00	5732.97	612.05	132.49	40.028643	-109.538968	0.37	94.00	626.15	
5876.00	2.24	80.32	5827.89	613.05	136.32	40.028646	-109.538954	0.53	95.00	628.00	
5971.00	1.29	126.33	5922.85	612.73	139.02	40.028645	-109.538945	1.72	95.00	628.29	
6065.00	0.63	172.53	6016.83	611.59	139.94	40.028642	-109.538941	1.03	94.00	627.39	
6159.00	0.64	178.65	6110.83	610.55	140.02	40.028639	-109.538941	0.07	94.00	626.40	
6254.00	0.72	161.88	6205.82	609.45	140.21	40.028636	-109.538940	0.22	95.00	625.37	
6348.00	1.10	168.24	6299.81	10.809	140.58	40.028632	-109.538939	0.42	94.00	624.05	
6443.00	0.50	159.91	6394.80	606.73	140.91	40.028629	-109.538938	0.64	95.00	622.88	

	Œ
	-
	_
	~
	2—
	_
	_
	**
	~
	١.
	c
-	_
	æ
	\sim
	2.
	q.
	•
	~
- 6	_
- 8	
	-
	۳
	١.
	\overline{a}
	С
ı.	
	-
	<u>s_</u>
	dl'
	ë
	٠.
	'n
	щ
	Œ
- 4	
	>

centre, TVD relative to Drill Floor)
TVD (US ft)
6583.79
8677.78
6772.76 602.77
6866.76 603.01
6961.74 604.45
7056.74 605.17
7150.73 606.39
7245.71 608.31
7339.70 609.72
7434.68 611.43
7528.66 613.34
7622.65 614.75
7717.62 617.19
7811.56 620.13
8000.51 623.90
8189.50 625.53
8378.50 624.89
8567.48 622.58
8756.43 618.10
8851.39 615.46
9040.32 611.11
9135.29 609.00
9418.18 601.59
9702.04 593.92
9788.00 591.82
10140.81 582.96